

ADVERTISEMENT TO BIDDERS
FOR
SOUTHWEST DRINAGE 2011-D-1
BID SOLICITATION FOR PROJECT PIPE
CITY OF GRAND ISLAND, NEBRASKA

Sealed bids will be **received at the City Clerk's Office**, 100 East First Street, P.O. Box 1968, Grand Island, Nebraska, 68802, until **2:15 pm** (local time) on **September 7, 2011**, for **Southwest Drainage 2011-D-1 Project Pipe** for the City of Grand Island. Bids will be opened at this time in the Public Works Administration Suite, located on the second floor of City Hall. Bids received after the specified time will be returned unopened to sender.

Bids shall be submitted on forms which will be furnished by the City. **The envelope must be clearly marked indicating its contents. Failure to submit the necessary qualifying information in a clearly marked envelope will result in your bid not being opened or considered.**

Bids will be evaluated by the Purchaser based on price, quality, specification, and reputation of bidder.

The Purchaser reserves the right to reject any or all bids, to waive technicalities, and to accept whichever bid that may be in the best interest of the City at its sole discretion.

No bidder may withdraw said bid for a period of 45 days after date of bid opening.

Questions associated in preparing bids may be directed to the office of the City Engineer, Second Floor, City Hall, 100 East First Street, Grand Island, NE.

RaNae Edwards
City Clerk



SOUTHWEST DRAINAGE 2011-D-1
BID SOLICITATION FOR PROJECT PIPE

General Project Description of Work

The Southwest Drainage project has been divided into three phases. Phase I will construct the drainage outlet to the Wood River and includes pipe installation and ditch improvements east of U.S. Highway 281. Phase II includes improvements on U.S Highway 281 right-of-way and areas west of U.S. Highway 281. Phase III includes construction of a west detention cell as development occurs. With the Southwest Drainage outlet in place, the City of Grand Island will be able to modify the following storm drainage flow paths:

- Provide an outlet for the existing ditches located north and east of the Central Community College
- Provide an outlet for U.S Highway 281 right-of-way and low lying areas adjacent to the highway
- Divert the Brentwood Lake outlet flow from the Stolley Park storm sewer system to the proposed Southwest Drainage outlet
- Modify the Case New Holland outlet to flow to the proposed Southwest Drainage outlet

***All Pipe shall be Class III**

****The concrete shall be air-entrained as specified in the City of Grand Island Standard Specifications - Division III, Curb and Gutter, Sidewalks, and Driveways**

<u>Description</u>	<u>QUANTITY</u>	<u>Unit Price</u>	<u>Total Price</u>
1. 60" Round Equivalent Reinforced Concrete Storm Sewer Pipe (RCP)	762.0 l.f.	\$ _____	\$ _____
2. 60" Reinforced Concrete Storm Sewer Pipe (RCP)	58.0 l.f.	\$ _____	\$ _____
3. 48" Reinforced Concrete Storm Sewer Pipe (RCP)	222.0 l.f.	\$ _____	\$ _____
4. 36" Reinforced Concrete Storm Sewer Pipe (RCP)	144.0 l.f.	\$ _____	\$ _____
5. 15" Reinforced Concrete Storm Sewer Pipe (RCP)	81.0 l.f.	\$ _____	\$ _____
6. 60" Round Equivalent Reinforced Concrete Flared End Section	1.0 ea.	\$ _____	\$ _____
7. 60" Reinforced Concrete Flared End Section	1.0 ea.	\$ _____	\$ _____

SOUTHWEST DRAINAGE 2011-D-1
BID SOLICITATION FOR PROJECT PIPE

8. 48" Reinforced Concrete Flared End Section	4.0 ea.	\$ _____	\$ _____
9. 36" Reinforced Concrete Flared End Section	8.0 ea.	\$ _____	\$ _____

Total Bid \$ _____

Bids are due no later than 2:15 p.m. on Wednesday, September 7, 2011.

Pipe shall be delivered to project site by October 14, 2011.

Name of Bidder _____

Address _____

Phone # _____

Date _____