CHIP SEAL PROJECT NO. 2012-CS-1

FOR

CITY OF GRAND ISLAND, NEBRASKA

CONTRACT DOCUMENTS AND SPECIFICATIONS

FEBRUARY 2012



ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS GRAND ISLAND, NEBRASKA

BIDDER CHECKLIST FOR

CHIP SEAL PROJECT NO. 2012-CS-1

CITY OF GRAND ISLAND, NEBRASKA

Bids must be received by the City Clerk before 2:00 p.m., (local time) on Wednesday, February 29, 2012.


Γhe fo	llow	wing items must be completed for your bid to be co	nsidered.
	Î	A completed bidder checklist form.	
	Ĩ	A signed original and one copy of the Contractor	r's Bid. (Pages CB-1 through CB-4)
	Î	Acknowledgment of Addenda Number(s)	·
	í	Firm unit pricing; or lump sum pricing as application	able. (See bid Form)
	Ĩ	A certified check, cashiers check or bid bond in outside of the envelope containing the bid. Eat indicating its contents. Failure to submit the nec clearly marked and separate envelopes will result	ich envelope must be clearly marked eessary qualifying information in
Bidde	r Co	Company Name	Date
Print -	- Na	lame of Person Completing Bid	
Signat	ure	е	

CHIP SEAL PROJECT NO. 2012-CS-1

CITY OF GRAND ISLAND, NEBRASKA

TABLE OF CONTENTS

- 1 Bidder Checklist
- 2. Table of Contents
- 3. Advertisement to Bidders
- 4. Contractor's Bid
- 5. Instructions to Bidders
- 6. Insurance Requirements
- 7. Exempt Sales Certificate
- 8. Purchasing Agent Appointment
- 9. Contract Agreement
- 10. Division I General Specifications
- 11. Division IA Special Provisions



ADVERTISEMENT TO BIDDERS for

CHIP SEAL PROJECT NO. 2012-CS-1

for CITY OF GRAND ISLAND, NEBRASKA

Sealed bids will be received at the office of the City Clerk, 100 E. First Street., Grand Island, NE 68801 or P.O. Box 1968, Grand Island, Nebraska 68802 until 2:00 p.m., (Local Time), Wednesday, February 29, 2012, for the construction of Chip Seal Project No. 2012-CS-1 for the City of Grand Island. Bids will be publicly opened at this time in the Conference Room #1 located on 1st floor of City Hall. Bids received after specified time will be returned unopened to sender.

Bids shall be submitted on forms which will be furnished by the City. Each bidder shall submit with their bid a certified check, a cashiers check or bid bond payable to the City Treasurer in an amount no less than five percent (5%) of the bid price which shall guarantee good faith on the part of the bidder and the entering into a contract within 15 days, at the bid price, after acceptance by the City. "Your certified check, cashiers check or bid bond must be submitted in a separate envelope attached to the outside of the envelope containing the bid." Each envelope must be clearly marked indicating its contents. Failure to submit the necessary qualifying information in clearly marked and separate envelopes will result in your bid not being opened or considered. Bid bonds must be issued by surety companies authorized to do business in the State of Nebraska. Please return one original and one copy of each bid sheet.

The successful bidder will be required to comply with fair labor standards as required by Nebraska R.R.S. 73-102 and comply with Nebraska R.R.S. 48-657 pertaining to contributions to the Unemployment Compensation Fund of the State of Nebraska.

Successful bidder shall comply with the City's insurance requirements, and supply performance and payment bonds. Successful bidder shall maintain a Drug Free Workplace Policy.

Bids will be evaluated by the Purchaser based on price, quality, adherence to schedule, plan and specification, economy and efficiency of operation, experience and reputation of bidder, ability, capacity, and skill of the bidder to perform contract required and adaptability of the particular items to the specific use intended.

The Purchaser reserves the right to reject any or all bids and to waive irregularities therein and to accept whichever bid that may be in the best interest of the City, at its sole discretion.

GRATUITIES AND KICKBACKS: City Code states that it is unethical for any person to offer, give, or agree to give any City employee or former City employee, or for any City employee or former City employee to solicit, demand, accept, or agree to accept from another person, a gratuity or an offer of employment in connection with any decision, approval, disapproval, recommendation, or preparation of any part of a program requirement or a purchase request, influencing the content of any specification or procurement standard, rendering of advice, investigation, auditing, or in any other advisory capacity in any proceeding or application, request for ruling, determination, claim or controversy, or other particular matter, pertaining to any program requirement or a contract or subcontract, or to any solicitation or proposal therefore. It shall be unethical for any payment, gratuity, or offer of employment to be made by or on behalf of a subcontractor under a contract to the prime contractor or higher tier subcontractor or any person associated therewith, as an inducement for the award of a subcontract to order.

No bidder may withdraw their bid for a period of forty-five (45) days after date of opening bids.

TITLE VI: The City of Grand Island, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C 2000d to 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office the Secretary, Part 21, Nondiscrimination in Federally assisted programs of the Department of Transportation issued pursuant to such Act, hereby notified all bidden that it will affirmatively insure that in any contact entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation

and will not be discriminated against on the grounds of race, color, or national origin, sex, age and disability/handicap in consideration for an award.


SECTION 504/ADA NOTICE TO THE PUBLIC: The City of Grand Island does not discriminate on the basis of disability in admission of its programs, services, or activities, in access to them, in treatment of individuals with disabilities, or in any aspect of their operations. The City of Grand Island also does not discriminate on the basis of disability in its hiring or employment practices.

This notice is provided as required by Title II of the Americans with Disabilities Act of 1990 and Section 504 of the Rehabilitation Act of 1973. Questions, complaints, or requests for additional information or accommodation regarding the ADA and Section 504 may be forwarded to the designated ADA and Section 504 compliance coordinator.

Mary Lou Brown 308-385-5444, extension 140 100 East First Street, Grand Island, NE 68801 Monday through Friday; 8:00 a.m. to 5:00 p.m.

Plans and specifications for use in preparing bids may be obtained from the office of the City Engineer, Second Floor, City Hall, 100 East First Street, Grand Island, NE.

RaNae Edwards City Clerk



CHIP SEAL PROJECT NO. 2012-CS-1

CITY OF GRAND ISLAND, NEBRASKA

CONTRACTOR'S BID

TO THE MEMBERS OF THE COUNCIL CITY OF GRAND ISLAND GRAND ISLAND, NEBRASKA

THE UNDERSIGNED BIDDER, having examined the plans, specifications, general and special conditions, and other proposed contract documents, and all addenda thereto and being acquainted with and fully understanding (a) the extent and character of the work covered by this Bid, (b) the location, arrangement, and specified requirements for the proposed work, (c) the location, character, and condition of existing streets, roads, highways, railroad, pavements, surfacing, walks, driveways, curbs, gutters, trees, sewers, utilities, drainage courses and structures, and other installations, both surface and underground which may affect or be affected by the proposed work, (d) the nature and extent of the excavations to be made and the handling and re-handling of excavated materials, (e) the location and extent of necessary or probable dewatering requirements, (f) the difficulties and hazards to the work which might be caused by storm and flood water, (g) local conditions relative to labor, transportation, hauling and rail delivery facilities, and (h) all other factors and conditions affecting or which may be affected by the work.

HEREBY PROPOSES to furnish all required materials, supplies, equipment, tools and plans, to perform all necessary labor and supervision, and to construct, install, erect, equip and complete all work stipulated in, required by and in accordance with the contract documents and the plans, specifications and other documents referred to therein (as altered, amended or modified by all addenda thereto) for and in consideration of the following prices:

BID SECTION -

No.	Description	Estimated Quantity	<u>Unit</u>	Firm <u>Unit Price</u>	Total Price
1.	Chip Seal Aggregate	240.0	c.y.	\$	\$
2.	Chip Seal Emulsified Asphalt	8,000.0	gal	\$	\$
3.	Temporary Sign Day	80.0	ea.	\$	\$
4.	Barricade, Type II	60.0	bday	\$	\$
5.	Barricade, Type III	45.0	bday	\$	\$
6.	Temporary Raised Pavement Marker (Yellow)	600.0	ea.	\$	\$
7.	Temporary Raised Pavement Marker (White)	180.0	ea.	\$	\$
8.	Flagging	15.0	day	\$	\$
9.	Mobilization	1.0	1.s.	\$	\$
		GRAND	TOTAL BID :	= \$	

GRAND TOTAL BID = S_____


The City reserves the right to reject any bid section(s) submitted by the successful bidder. The bid award selection will be based on the Grand Total Bid for the project, with sections being completed as budgeted funds allow.

EXPERIENCE DATA:	e de la companya de		:		
Each bidder shall supply the following	ng data on their e	experience:			
Name of Bidder:	*1		e*.		
Project Owner/Contact/Phone No.	Proje	et Location		Completion Date	

Additional Data:	* .			· · · · · · · · · · · · · · · · · · ·	
	•				
INSURANCE: Bidder acknowledg ADDENDA: Bidder acknowledges that the follow		-		-	
ADDENDUM NO.	<u>DATE</u>		SIGNATU	URE	
		_			
					
Exceptions shall be listed in the following for the following supplementary terms. Failure to our bidder to comply with these specifications shall govern unless specifications.	d. Reference <u>s</u> atline such exceptications. In case	hall not be motions as specified of conflict be	ade to other ically stated etween the	er attachments for of the desired herein will require	exceptions and the successful
Exceptions to specifications, pages _			······································		

The undersigned bidder agrees to furnish the required performance & payment bond and to enter into a contract within 15 days after acceptance of this Bid, and further agrees to complete all work covered by the foregoing bid in accordance with specified requirements. No work shall commence until the Certificate of Insurance and bonds (when required) are approved by the City and the contract is executed. The proposed work can commence after the contract is signed and the required bond is approved. The work in this contract shall be completed before September 30, 2012.
Enclosed herewith is the required bid guarantee in the amount of
which the undersigned bidder agrees is to be forfeited to and become the property of the City of Grand Island Nebraska, as liquidated damages should this Bid be accepted and a contract be awarded to them and they fail to enter into a contract in the form prescribed and to furnish the required bond within 15 days, but otherwise the aforesaid bid guarantee will be returned upon signing the contract and delivering the approved bond
In submitting the bid it is understood that the right is reserved by the City to reject any and all bids; to waive irregularities therein and to accept whichever bid that may be in the best interest of the City. It is understood that this bid may not be withdrawn by the bidder until after 45 days from bid opening.
In submitting the bid, the bidder states that bidder fully complies with, and will continue to comply with, applicable State fair labor standards as required by section 73-102 RRS, 1943 and also complies with, and will continue to comply with, section 48-657 RRS, 1943 pertaining to contributions to the Unemployment Compensation Fund of the State of Nebraska.
The undersigned bidder hereby certifies (a) that this bid is genuine and is not made in the interest of or in the behalt of any undisclosed person, firm or corporation, and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation, (b) that they have not directly or indirectly induced or solicited any person, firm or corporation to refrain from bidding, (c) that they have not sought, by collusion or otherwise, to obtain for themselves an advantage over any other bidder or over the City of Grand Island, and (d) that they have not directly or indirectly induced or solicited any other bidder to put in a false or sham bid.
DATED
SIGNATURE OF BIDDER: If an Individual: doing business
as
by, member of firm.
If a Corporation:

by	(Seal)
Title	
	·
BUSINESS ADDRESS OF BIDDER	
TELEPHONE NUMBER OF BIDDER	FAX NUMBER OF BIDDER



INSTRUCTIONS TO BIDDERS

CHIP SEAL PROJECT NO. 2012-CS-1

CITY OF GRAND ISLAND, NEBRASKA

EXCEPTIONS TO SPECIFICATIONS: Each bidder shall carefully check all requirements herein set forth and shall offer items which fully comply with these requirements or shall plainly set forth all points, features, conditions, specifications.

SUBMISSION OF BIDS: All bids shall be submitted using the City's bid form. Bids shall be addressed to the City Clerk and plainly marked, "BID FOR CHIP SEAL PROJECT NO. 2012-CS-1".

INSURANCE COVERAGE: The Contractor shall purchase and maintain at their expense as a minimum insurance coverage of such types and in such amounts as are specified herein to protect Contractor and the interest of Owner and others from claims which may arise out of or result from Contractor's operations under the Contract Documents, whether such operations be by Contractor or by any subcontractor or anyone directly or indirectly employed by any of them or for whose acts any of them may be legally liable. Failure of Contractor to maintain proper insurance coverage shall not relieve them of any contractual responsibility or obligation.

BASE BID: The bidder is expected to base their bids on materials and items complying fully with these specifications, and in the event the contractor names in the bid materials items which do not conform, they will be responsible for furnishing materials and items which fully conform at no change in the bid price.

BIDDER QUALIFICATION: Bids will be received only from qualified bidders. A bidder will be considered qualified if they are a recognized manufacturer or supplier of materials and items similar to that specified herein with complete factory facilities in the United States and has had experience in the design and manufacture of items of equal or greater size than that specified herein. If requested, the Bidder shall supply experience data. Such data will be used to assist in determining the qualifications of the Bidder. Bidder must comply with all applicable Federal, State and Local rules and regulations.

GRATUITIES AND KICKBACKS: City Code states that it is unethical for any person to offer, give, or agree to give any City employee or former City employee, or for any City employee or former City employee to solicit, demand, accept, or agree to accept from another person, a gratuity or an offer of employment in connection with any decision, approval, disapproval, recommendation, or preparation of any part of a program requirement or a purchase request, influencing the content of any specification or procurement standard, rendering of advice, investigation, auditing, or in any other advisory capacity in any proceeding or application, request for ruling, determination, claim or controversy, or other particular matter, pertaining to any program requirement or a contract or subcontract, or to any solicitation or proposal therefore. It shall be unethical for any payment, gratuity, or offer of employment to be made by or on behalf of a subcontractor under a contract to the prime contractor or higher tier subcontractor or any person associated therewith, as an inducement for the award of a subcontract to order.

CHECKS OR BID BONDS: Checks or bid bonds of the unsuccessful bidders will be returned when their bids have been rejected and not to exceed 45 days from the date bids are opened. All bids shall remain in force for this 45-day Period. The check or bid bond of the successful bidder will be returned when the Contracts are signed by both parties and necessary bonds supplied. Should the Purchaser make an award to a Contractor who refuses to enter into Contract and furnish the required bonds within 15 days after notification of acceptance, then the bid security which has been deposited with the Purchaser will be forfeited to the Purchaser as liquidated damages.

PERFORMANCE BOND: When required, on award of the Contract, the successful Contractor shall furnish a Performance Bond which shall be in an amount equal to the full Contract price, guaranteeing faithful compliance with all requirements of the Contract Documents and complete fulfillment of the Contract, and payment of all labor, material and other bills incurred in carrying out this Contract. According to Nebraska Law, the surety company executing the Performance Bond must be authorized to do business in the State of Nebraska.

PAYMENT BOND: When required, on award of the Contract, the successful Contractor shall furnish a Payment Bond which shall be in an amount equal to the full Contract price, guaranteeing protection of all persons supplying labor and materials to the Contractor or its subcontractors for the performance of the work provided for in the Contract. In accordance with Nebraska Law, the surety company executing the Payment Bond must be authorized to do business in the State of Nebraska.

TAXES: The City of Grand Island is exempt from paying local City and State Sales Tax for materials incorporated into the work. Refer to Exempt Sale Certificate enclosed for your information. Contractor must pay any other tax which might be applicable.

REQUESTS FOR PAYMENT: The City of Grand Island will make payments only after approval at regularly scheduled City Council meetings. These meetings typically occur the second and fourth Monday each month. Requests for payment must be received no less than ten working days prior to the designated meeting to allow proper review and consideration. Progress Payments will be permitted during the project, so long as work is being done to the City's satisfaction unless otherwise stated in bidding documents.

REQUEST FOR INTERPRETATION: If any person, contemplating submitting a bid for this Contract is in doubt as to the true meaning of any part of the specifications or other proposed Contract documents, they may submit to the Purchasing Department a written request for an interpretation thereof. The person submitting the request will be responsible for its prompt delivery. Any interpretation of the proposed documents will be made only by addendum only issued and/or delivered to each person receiving a set of such documents. The addenda upon closing shall become a part of the Contract. The Purchasing Department will not be responsible for any other explanation or interpretation of the proposed documents.

TIME OF COMPLETION: This work in this contract shall be completed before September 30, 2012.

CLEANING UP: Contractor shall maintain a clean and safe work area while on site.

ADDENDA: Any addendum to the specifications issued during the time allowed for preparation of bids shall be covered in the bid and shall become a part of the specifications. Addendums issued before the date of the letting will be sent to all bidders. One signed copy is to be returned immediately to the Purchasing Department (or other department if so designated in the Addendum) as acknowledgment of receipt.

MODIFICATION OF BIDS: Bids may be modified or withdrawn by an appropriate document duly executed in the manner that a bid must be executed and delivered to the place where bids are to be submitted at any time prior to the final time set for receiving bids. Bidders may modify or withdraw bids by Fax communication at any time prior to the time set for receiving bids provided this instruction is positively identified. Any Fax modification should not reveal the amended bid price but should provide only the addition, subtraction or other modifications. A duly-executed document confirming the Fax modification shall be submitted within three days after bids are opened.

BID DATA: Bidders shall submit bid data, if required, on items offered in the Bid by furnishing one original and one copy of the completed Contractor's Bid form. The bid sheets shall be filled out legibly in <u>ink</u> to permit reproduction.

BIDDER SECURITY: Bidder security, when required, shall be enclosed in a special envelope marked, "BIDDER SECURITY/BID FOR CHIP SEAL PROJECT NO. 2012-CS-1". The envelope shall contain only a cashier's check, certified check or bidder's bond.

This special envelope shall be attached to a sealed envelope containing the bid and any other bid materials. This second envelope shall be "BID FOR CHIP SEAL PROJECT NO. 2012-CS-1" and be addressed to the City Clerk." Bids of an incomplete nature or subject to multiple interpretation may, at the option of the Purchaser, be rejected as being irregular.

FINANCIAL STATEMENT: The bidder shall furnish, upon request, a complete financial statement signed by the bidder, if an individual, by all partners if the bidder is a partnership and, by the President or Secretary, if the bidder is a corporation.

DRUG FREE WORKPLACE POLICY: Bidders shall furnish, upon request, a copy of their Drug Free workplace Policy.

EQUAL EMPLOYMENT OPPORTUNITY: The Contractor agrees that during the performance of this Contract not to discriminate in hiring or any other employment practice on the basis of race, color, religion, sex, disability, age or national origin, and to comply with Executive Order 11,246 of September 24, 1965, and the rules, regulations and relevant orders of the Secretary of Labor, and Chapter 20 of the Reissue Revised Statutes of the State of Nebraska.

LOCAL CONDITIONS: Each bidder shall have an authorized representative visit the site of the work and thoroughly inform them of all conditions and factors which would affect the work and the cost thereof, including the arrangement and conditions of existing or proposed structures affecting or affected by the proposed work; the procedure necessary for maintenance of uninterrupted operation; the availability and cost of labor and facilities for transportation, handling, and storage of materials and equipment.

TILE VI: The City of Grand Island, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C 2000d to 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office the Secretary, Part 21, Nondiscrimination in Federally assisted programs of the Department of Transportation issued pursuant to such Act, hereby notified all bidden that it will affirmatively insure that in any contact entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin, sex, age and disability/handicap in consideration for an award.

SECTION 504/ADA NOTICE TO THE PUBLIC: The City of Grand Island does not discriminate on the basis of disability in admission of its programs, services, or activities, in access to them, in treatment of individuals with disabilities, or in any aspect of their operations. The City of Grand Island also does not discriminate on the basis of disability in its hiring or employment practices.

This notice is provided as required by Title II of the Americans with Disabilities Act of 1990 and Section 504 of the Rehabilitation Act of 1973. Questions, complaints, or requests for additional information or accommodation regarding the ADA and Section 504 may be forwarded to the designated ADA and Section 504 compliance coordinator.

Mary Lou Brown 308-385-5444, extension 140 100 East First Street, Grand Island, NE 68801 Monday through Friday; 8:00 a.m. to 5:00 p.m.

It must be understood and agreed that all such factors have been investigated and considered in the preparation of every bid submitted. No claims for financial adjustment (to any Contract awarded for the work under these Specifications and documents) will be permitted by the City, which are based on lack of such prior information, or its effect on the cost of the work.


CORRESPONDENCE: Correspondence regarding drawings, instruction manuals, and other engineering data shall be clearly marked "FOR ENGINEERING DEPARTMENT" and sent through:

City of Grand Island Public Works Department/Engineering Division P.O. Box 1968 Grand Island, NE 68802-1968 (308) 385-5444, Extension 260 Attn: Terry Brown

LOCAL BIDDER PREFERENCE: In case of tied low bids, all other things being equal, preference shall be given in the following order:

- 1. To those bidders who manufacture their products within the limits of the City of Grand Island.
- 2. To those bidders who manufacture their products within the limits of the County of Hall.
- 3. To those bidders who package, process, or through some other substantial operation have employees and facilities for these purposes in the City of Grand Island.
- 4. To those bidders who package, process, or through some other substantial operation have employees and facilities for these purposes in the County of Hall.
- 5. To those bidders who maintain a bona fide business office in the City of Grand Island, whose products may be made outside the confines of the City of Grand Island.
- 6. To those bidders who maintain a bona fide business office in the County of Hall, whose products may be made outside the confines of the County of Hall.

- 7. To those bidders whose commodities are manufactured, mined, produced, or grown within the State of Nebraska, and to all firms, corporations, or individuals doing business as Nebraska firms, corporations or individuals, when quality is equal or better, and delivered price is the same or less than the other bids received.
- 8. To those bidders whose commodities are manufactured, mined, produced, or grown within the United States of America, and to all firms, corporations, or individuals doing business as firms registered in states other than Nebraska, when quality is equal or better, and delivered price is the same or less than the other bids received.



MINIMUM INSURANCE REQUIREMENTS

CHIP SEAL PROJECT NO. 2012-CS-1

CITY OF GRAND ISLAND, NEBRASKA

You are urged to include in your bid compliance with the City's minimum insurance requirements; however, any non-compliance must be detailed in the Exceptions Section of the bid. Compliance with the specified OCP coverage is mandatory.

The successful bidder shall obtain insurance from companies authorized to do business in Nebraska of such types and in such amounts as may be necessary to protect the bidder and the interests of the City against hazards or risks of loss as hereinafter specified. This insurance shall cover all aspects of the Bidder's operations and completed operations. Failure to maintain adequate coverage shall not relieve bidder of any contractual responsibility or obligation. Minimum insurance coverage shall be the amounts stated herein or the amounts required by applicable law, whichever are greater.

1. WORKERS COMPENSATION AND EMPLOYER'S LIABILITY

This insurance shall protect the Bidder against all claims under applicable State workers compensation laws. This insurance shall provide coverage in every state in which work for this project might be conducted. The liability limits shall not be less than the following:

Workers Compensation Employers Liability Statutory Limits \$100,000 each accident \$100,000 each employee \$500,000 policy limit

2. BUSINESS AUTOMOBILE LIABILITY

This insurance shall be written in comprehensive form and shall protect the Bidder, Bidder's employees, or subcontractors from claims due to the ownership, maintenance, or use of a motor vehicle. The liability limits shall be not less than the following:

Bodily Injury & Property Damage

\$ 500,000 Combined Single Limit

3. COMPREHENSIVE GENERAL LIABILITY

The comprehensive general liability coverage shall contain no exclusion relative to explosion, collapse, or underground property. The liability limits shall be not less than the following:

Bodily Injury & Property Damage

\$ 500,000 each occurrence \$1,000,000 aggregate

4. UMBRELLA LIABILITY INSURANCE

This insurance shall protect the Bidder against claims in excess of the limits provided under employer's liability, comprehensive automobile liability, and commercial general liability policies. The umbrella policy shall follow the form of the primary insurance, including the application of the primary limits. The liability limits shall not be less than the following:

Bodily Injury & Property Damage

\$1,000,000 each occurrence \$1,000,000 general aggregate

5. ADDITIONAL REQUIREMENTS

The City may require insurance covering a Bidder or subcontractor more or less than the standard requirements set forth herein depending upon the character and extent of the work to be performed by such Bidder or subcontractor.

Insurance as herein required shall be maintained in force until the City releases the Bidder of all obligations under the Contract.

The Bidder shall provide and carry any additional insurance as may be required by special provisions of these specifications.

6. CERTIFICATE OF INSURANCE

Satisfactory certificates of insurance shall be filed with the City prior to starting any work on this Contract. The certificates shall show the City as an additional insured on all coverage except Workers Compensation. The certificate shall state that thirty (30) days written notice shall be given to the City before any policy is cancelled (strike the "endeavor to" wording often shown on certificate forms). If the bidder cannot have the "endeavor to" language stricken, the bidder may elect to provide a new certificate of insurance every 30 days during the contract. Bidder shall immediately notify the City if there is any reduction of coverage because of revised limits or claims paid which affect the aggregate of any policy.





Nebraska Resale or Exempt Sale Certificate for Sales Tax Exemption

Read instructions on reverse side/see note below

FORM

13

NAME AND MAILING ADDRESS OF PURCHASER		NAME AND MAILING ADDRESS OF SELLER					
Name				Name			
Street or Other	r Mailing Address			Street or Oth	er Mailing Address		
							Zin Codo
ity		State	Zip Code	City		State	Zip Code
heck Type of			011 1 1 1	1 (1) 22	is vestid until rous	dead in writing by t	he mirchaser
	Single Purchase	Blanket I	t blanket is checke	d, this certific	cate is valid until reve	weeks color toy for	the following reason
I her	reby certify that the pure					Contractor	(Complete Section C)
heck One	Purchase for Resal	e (Complete Section	A) Lexemp	t Purchase (C	Complete Section B)	Contractor	(Complete Section C)
		SECTIO			le Certificate		
from the a	beby certify that the purchase above seller is exempt from the ondition in which purchase	m the Nebraska sale	s tax as a purchase int or component p	for resale, re art of other p	ental, or lease in the n roperty to be resold.	ormal course of our	business, either in the
I fur	ther certify that we are en ription of Product Sold, Leased	gaged in business as		olesaler 🗌	Retailer 🗌 Manu	facturer Lesso	or
				lf N	one, State Reason		
and hold	Nebraska Sales Tax Permi	it Number 01-					
or Foreig	n State Sales Tax Number				State		
		SECTION I	3 — Nebraska	a Exempt	Sale Certificat	e	
If ex	basis for this exemption is comption category 2 or 5 is f Item(s) Purchased				se of Item(s) Purchased		
If ex	xemption categories 3 or 4	are claimed, enter t	he Nebraska Exem	ption Certific	cate number. 05 -		
Ifex	kemption category 6 is cla	imed, seller must en	ter the following i	nformation as	nd sign this form belo	w:	
Description of			Date of Seller's Origin		Was Tax Paid when	Purchased by Seller?	Was Item Depreciable?
		SEC	TION C—Fo	r Contrac			
d Downhau	ses of Building Materi		THORE IT	. ,		-	
As an C	Option 1 or Option 3 contr ka sales tax. My Nebraska	actor, I hereby certi	fy that purchases o 's Use Tax Permit	of building ma Number is:	aterials and fixtures fi	rom the above selle	r are exempt from
2. Purcha	ses Made Under Purch	nasing Agent App	ointment on be	half of		(exempt entity)	
		ing Agent Appointm	ent and Delegation		for Sales and Use Ta		y certify that purchase
Pursua of build	ding materials, and fixture						
Pursua of build	ding materials, and fixture	r agent, or other person ser's business, or is not interest, or penalty othe	who completes this otherwise exempted rwise imposed, be sured to a blanket certific	trom the sales a object to a pena ate this negalty	ity of \$100 or ten times shall apply to each purch	the tax, whichever amonase made during the p	ount is larger, for eriod the blanket
Pursual of build	Any purchaser, or thei regular course of the purcha shall in addition to any tax, each instance of presentatio certificate is in effect. Under	r agent, or other person ser's business, or is not interest, or penalty othe	who completes this otherwise exempted rwise imposed, be sured to a blanket certific	trom the sales a object to a pena ate this negalty	and use tax under Neb. to lity of \$100 or ten times shall apply to each purch	the tax, whichever amonase made during the p	ount is larger, for eriod the blanket

NOTE: Sellers must keep this certificate as part of their records. DO NOT SEND TO THE NEBRASKA DEPARTMENT OF REVENUE. Incomplete certificates cannot be accepted.

INSTRUCTIONS

WHO MAY ISSUE A RESALE CERTIFICATE. Form 13, Section A, is to be issued by persons or organizations making purchases of property or taxable services in the **normal** course of their business for the purpose of resale either in the form or condition in which it was purchased, or as an ingredient or component part of other property.

WHO MAY ISSUE AN EXEMPT SALE CERTIFICATE.

Form 13, Section B can only be issued by persons or organizations exempt from payment of the Nebraska sales tax by qualifying for one of the six enumerated Categories of Exemption (see below). Nonprofit organizations that have a 501(c) designation and are exempt from federal and state income tax are not automatically exempt from sales tax. Only the entities listed in the referenced regulations are exempt from paying Nebraska sales tax on their purchases when the exemption certificate is properly completed and provided to the seller. Organizations claiming a sales tax exemption may do so only on items purchased for their own use. For health care organizations, the exemption is limited to the specific level of health care they are licensed for. The exemption is not issued to the entire organization when multiple levels of health care or other activities are provided or owned by the organization. Items purchased by an exempt organization that will be resold must be supported by a properly completed Nebraska Resale Certificate, Form 13, Section A.

Indicate the category which properly reflects the basis for your exemption. Place the corresponding number in the space provided in Section B. If category 2 through 6 is the basis for exemption, you must complete the information requested in Section B.

Nebraska Sales and Use Tax Reg-1-013. Sale for Resale — Resale Certificate, and Reg-1-014. Exempt Sale Certificate, provide additional information on the proper issuance and use of this certificate. These and other regulations referred to in these instructions are available on our Web site: www.revenue.ne.gov/legal/regs/slstaxregs.

Use Form 13E for purchases of energy sources which qualify for exemption. Use Form 13ME for purchases of mobility enhancing equipment on a motor vehicle.

CONTRACTORS. Form 13, Section C, Part 1, must be completed by contractors operating under Option 1 or Option 3 to document their tax-free purchase of building materials or fixtures from their suppliers. Section C, Part 2, may be completed to exempt the purchase of building materials or fixtures pursuant to a <u>Purchasing Agent Appointment</u>, Form 17. See the <u>contractor information guides</u> on our Web site **www.revenue.ne.gov** for additional information.

WHERE TO FILE. Form 13 is given to the seller at the time of the purchase of the property or service or when sales tax is due. The certificate must be retained with the seller's records for audit purposes. Do not send to the Department of Revenue.

SALES TAX NUMBER. A purchaser who completes Section A and is engaged in business as a wholesaler or manufacturer is not required to provide an identification number. Out-of-state purchasers can provide their home state sales tax number. Section B does not require an identification number when exemption category 1, 2, or 5 is indicated.

PROPERLY COMPLETED CERTIFICATE. A purchaser must complete a certificate before issuing it to the seller. To properly complete the certificate, the purchaser must include: (1) identification of the purchaser and seller, (2) a statement whether the certificate is for a single purchase or is a blanket certificate,

(3) a statement of basis for exemption including completion of all information for the basis chosen, (4) the signature of an authorized person, and (5) the date the certificate was issued.

PENALTIES. Any purchaser who gives a Form 13 to a seller for any purchase which is other than for resale, lease, or rental in the **normal** course of the purchaser's business, or is not otherwise exempted from sales and use tax under the Nebraska Revenue Act, shall be subject to a penalty of \$100 or ten times the tax, whichever amount is larger, for each instance of presentation and misuse.

Any purchaser, or their agent, who fraudulently signs a Form 13 may be found guilty of a Class IV misdemeanor.

CATEGORIES OF EXEMPTION

1. Purchases made directly by certain governmental agencies identified in Nebraska Sales and Use Tax Reg-1-012, Exemptions; Reg-1-072, United States Government and Federal Corporations; and Reg-1-093. Governmental Units, are exempt from sales tax. A list of specific governmental units are provided in the above regulations. Governmental units are not assigned exemption numbers.

Sales to the United States government, its agencies, and corporations wholly owned by the United States government are exempt from sales tax. However, sales to institutions chartered or created under federal authority, but which are not directly operated and controlled by the United States government for the benefit of the public, generally are taxable. Construction projects for federal agencies have specific requirements, see <u>Reg-1-017</u> Contractors.

Purchases that are **not** exempt from Nebraska sales and use tax include, but are not limited to, governmental units of other states, sanitary and improvement districts, urban renewal authorities, rural water districts, railroad transportation safety districts, and county historical or agricultural societies.

- 2. Purchases when the intended use renders it exempt as set out in paragraph 012.02D of Reg-1-012, Exemptions. Complete the description of the item purchased and the intended use as required on the front of Form 13. Sellers of repair parts for agricultural machinery and equipment cannot accept a Form 13 to exempt such sales from tax.
- 3. Purchases made by organizations that have been issued a Nebraska Exempt Organization Certificate of Exemption are exempt from sales tax. Reg-1-090, Nonprofit Organizations; Reg-1-091, Religious Organizations; and Reg-1-092, Educational Institutions, identify such organizations. These organizations will be issued a Nebraska state exemption identification number. This exemption number must be entered in Section B of the Form 13.
- **4.** Purchases of common or contract carrier vehicles and repair and replacement parts for such vehicles.
- 5. Purchases of manufacturing machinery or equipment by a taxpayer engaged in business as a manufacturer for use predominantly in manufacturing. This includes the installation, repair, or maintenance of such qualified manufacturing machinery or equipment (see <u>Revenue Ruling 01-08-2</u>).
- **6.** A sale that qualifies as an occasional sale, such as a sale of depreciable machinery and equipment productively used by the seller for more than one year and the seller previously paid tax on the item. The **seller** must sign and give the exemption certificate to the purchaser. The certificate must be retained by the purchaser for audit purposes (see <u>Reg-1-014</u>, <u>Exempt Sale Certificate</u>).

PURCHASING AGENT APPOINTMENT TAX FORM 17



Purchasing Agent Appointment

and Delegation of Authority for Sales and Use Tax

FORM **17**

		PURCHASING AG	ENT APPOINTMENT			
Name a	nd Address of Prime Contra	ctor	Name and Address of Governmental Unit or Exempt Organization			
Name Street or Other Mailing Address			Name			
			Street or Other Mailing Address			
				State	Zip Code	
ty	State	Zip Code	City	State	2.15 0000	
Na	me and Location of Project		Appointment Information			
ame			Effective Date (see Instruction	3)		
reet or Other Mailing Addre	SS		Expiration Date			
ity	State	Zip Code	Nebraska Exemption Number	(Exempt Organizations Only)		
					ted about	
its agent to pur	chase and pay for building materi	als that will be annexed to	the above-named contractor and preal estate by them into the tax of Title	exempt construction project sta	Date	
its agent to pur	chase and pay for building materia	als that will be annexed to	Title	sagnific constitucion project ou		
sign here Authorized Sign	chase and pay for building material grature of Governmental Unit or E	als that will be annexed to exempt Organization	real estate by them into the tax t	sagnific constitucion project ou		
its agent to pur sign here Authorized Sign	chase and pay for building materia	als that will be annexed to exempt Organization	Title	TY		
its agent to pur sign Authorized Sign Name	chase and pay for building material gnature of Governmental Unit or E	als that will be annexed to exempt Organization	Title CONTRACTOR'S AUTHORI	TY		
its agent to pur sign here Authorized Sign Name lame street or Other Mailing Address	chase and pay for building material gnature of Governmental Unit or E	als that will be annexed to exempt Organization	Title CONTRACTOR'S AUTHORI Effective Date	TY		
its agent to pur Sign here Authorized Sign Name lame Street or Other Mailing Addre	chase and pay for building material gnature of Governmental Unit or E DELE and Address of Subcontractes	Exempt Organization EGATION OF PRIME (ctor Zip Code	Title CONTRACTOR'S AUTHORI' Effective Date Expiration Date Portion of Project	TY Delegation Information	Date	
Name Street or Other Mailing Addression The under to the above-in	gnature of Governmental Unit or E DELE and Address of Subcontract State ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime contractor hereby decreased and pay for building material ersigned prime prime contractor hereby decreased and pay for building material ersigned prime pr	exempt Organization EGATION OF PRIME (ctor Zip Code ielegates authority to act a	Title CONTRACTOR'S AUTHORI' Effective Date Expiration Date Portion of Project	TY Delegation Information	Date	

INSTRUCTIONS

who must file. Any governmental unit or organization that is exempt from sales and use tax may appoint as its agent a prime contractor to purchase building materials and/or fixtures that will be annexed to property that belongs to or will belong to the governmental unit or exempt organization pursuant to a construction contract with the governmental unit or exempt organization. The appointment of the prime contractor as its agent is completed by issuing a Purchasing Agent Appointment and Delegation of Authority for Sales and Use Tax, Form 17, to the prime contractor. The Form 17 is required to be given to the contractor BEFORE he or she annexes building materials. The governmental unit or exempt organization must identify the project (e.g., east wing, chapel construction, or new school auditorium). Most

nonprofit organizations are NOT exempt from sales tax in Nebraska. In addition, not all governmental units are exempt from Nebraska sales tax. Refer to <u>Contractor Information</u> on our Web site for additional information on exempt entities. A contractor can confirm the exempt status of a governmental unit or exempt organization by contacting the Nebraska Department of Revenue.

The exemption from the payment of the Nebraska and local option sales and use taxes only applies if the governmental unit or exempt organization directly, or through its contractor, pays for the building materials. **IMPORTANT NOTE:** When an organization that requires licensure in order to be exempt (i.e., nonprofit hospitals), but is not licensed at the time of the construction project, the exempt organization **CANNOT**

issue either a purchasing agent appointment or an exemption certificate. If the exempt organization becomes licensed upon completion of the project, it may apply for a refund of the tax paid or collected by the contractors.

WHENTO FILE. A prime contractor engaging in a construction project with a governmental unit or exempt organization must receive a properly completed and signed Form 17 BEFORE any building materials are annexed. If Form 17 is not issued, the contractor must pay the sales and use taxes and the governmental unit or exempt organization may obtain a refund of the taxes paid by the contractor.

WHERE TO FILE. A copy of the completed form should be retained by the governmental unit or exempt organization issuing the Form 17. The original is to be retained by the prime contractor. Copies of this form must be made by the prime contractor for delegation purposes to any subcontractors working on the project identified on this form.

APPOINTMENT INFORMATION. Enter the dates the purchasing agent appointment will become effective and when it will expire. This appointment will not allow any purchases without payment of the tax by the prime contractor or subcontractor before the effective date or after the expiration date. The dates the delegation becomes effective and the expiration dates must be completed. The phrase "upon completion" or similar phrase is not acceptable as an expiration date. The governmental unit or exempt organization may need to issue another Form 17 if the project is not completed within the prior "effective" and "expiration" dates. Exempt organizations must enter their Nebraska Sales and Use Tax Exemption number.

DELEGATION OF PRIME CONTRACTOR'S AUTHORITY.

The prime contractor may delegate his or her authority to act as the purchasing agent of the governmental unit or exempt organization to a subcontractor. The prime contractor must complete his or her copy of Form 17 for each subcontractor who is delegated authority to act as a purchasing agent. Reproductions of this delegation must be provided to the subcontractor, who must retain a copy for his or her records, and to the governmental unit or exempt organization.

Enter the dates the delegation of the subcontractor will become effective, when it will expire, and the portion of the project delegated. This delegation will not allow any purchases without payment of the tax by the subcontractor before the delegation date or after the expiration date. Any further delegation from a subcontractor to additional subcontractors must be delegated by providing a copy of the Form 17 that they received from the prime contractor and attaching it to a separate Form 17 with any further delegation to other subcontractors. The purchasing agent appointment is limited to the contractor's purchase of building materials and/or fixtures for the specific project and is only valid during the appointment dates shown on the Form 17.

EXEMPT SALE CERTIFICATE. A prime contractor who has been appointed to act as a purchasing agent by a governmental unit or exempt organization, and who hires a subcontractor operating as an Option 1 contractor, must provide to that subcontractor a completed copy of Form 17 and a Nebraska Resale or Exempt Sale Certificate, Form 13, with Section C,

Part 2, completed. The subcontractor will retain these forms in his or her records, and will not charge the contractor sales tax on any portion of the invoice involving the annexation of materials to the specific project identified on the Form 17. If these forms are not provided to the subcontractor operating under Option 1, the subcontractor must collect and remit sales tax on the charge for the separately stated building materials portion of the invoice. If the Option 1 subcontractor does not separately state the charge for the building materials from contractor labor, then the entire charge is taxable to the prime contractor.

Contractors operating under Option 2 (maintaining a tax-paid inventory) who have been issued a Form 17 from a governmental unit or an exempt organization, must furnish each vendor a copy of the Form 17 and a Form 13, completing Section C, Part 2, when purchasing building materials that will be annexed to real estate. Forms 13 and 17 must be retained with the vendor's and contractor's records for audit purposes. A contractor or subcontractor may reproduce copies of these documents which will be furnished to the vendors for each invoice or order made by them.

Invoices from vendors for the purchase of building materials by the contractor as purchasing agent, or the authorized subcontractor, must clearly identify that such purchase is for the specific Form 17 project.

CREDIT/REFUND OF SALES AND USETAX. A contractor or subcontractor who has been appointed as a purchasing agent before any materials are annexed, may withdraw sales or use tax-paid materials from inventory that will be annexed to real estate or used to repair property annexed to real estate and receive a credit for the sales or use tax amount previously paid on those materials.


The contractor or subcontractor may take a credit either against his or her current tax liability, or file a <u>Claim for Overpayment of Sales and Use Tax. Form 7</u>, and receive a refund of the sales or use tax paid on those materials.

TOOLS, EQUIPMENT, AND SUPPLIES. The purchase, rental, or lease of tools, supplies, or equipment (i.e., scaffolding, barricades, machinery, etc.) by a contractor for use in the completion of an exempt project CANNOT be purchased tax free, even if the contractor has been issued a Form 17. These items do not become annexed to the real estate.

OPTION 1 CONTRACTOR ONLY. If an Option 1 contractor is the **only** contractor involved in performing work for a governmental unit or exempt organization, a Form 17 is NOT required. The Option 1 contractor must only obtain a Form 13, Section B, from the exempt project owner.

PENALTY. Any person who signs this document with the intent to evade payment of tax is liable for the sales and use tax, interest, and penalty, and may be found guilty of a misdemeanor.

AUTHORIZED SIGNATURE. The purchasing agent appointment must be signed by an officer of the exempt organization or proper government official. The delegation of prime contractor's authority must be signed by the owner, partner, corporate officer, or other individual authorized to sign by a power of attorney on file with the Nebraska Department of Revenue.



CONTRACT AGREEMENT

CONTRACT AGREEMENT
THIS AGREEMENT made and entered into this day of, 2012, by and between hereinafter called the Contractor, and the City of Grand Island, Nebraska, hereinafter called the City.
Nebraska, hereinafter called the City.
WITNESSETH:
THAT, WHEREAS, in accordance with law, the City has caused contract documents to be prepared and an advertisement calling for bids to be published, for construction of Chip Seal Project No. 2012-CS-1 ; and
WHEREAS, the City, in the manner prescribed by law, has publicly opened, examined, and canvassed the proposals submitted, and has determined the aforesaid Contractor to be the lowest responsive bidder, and has duly awarded to the said Contractor a contract therefore, for the sum or sums named in the Contractor's bid, a copy thereof being attached to and made a part of this contract;
NOW, THEREFORE, in consideration of the compensation to be paid to the Contractor and of the mutual agreements herein contained, the parties have agreed and hereby agree, the City for itself and its successors, and the Contractor for itself or themselves, and its or their successors, as follows:
ARTICLE I. That the Contractor shall (a) furnish all tools, equipment, superintendence, transportation, and other construction materials, services and facilities; (b) furnish, as agent for the City, all materials, supplies and equipment specified and required to be incorporated in and form a permanent part of the completed work; (c) provide and perform all necessary labor; and (d) in a good substantial and workmanlike manner and in accordance with the requirements, stipulations, provisions, and conditions of the contract documents as listed in the attached General Specifications and Special Provisions, said documents forming the contract and being as fully a part thereof as if repeated verbatim herein, perform, execute, construct and complete all work included in and covered by the City's official award of this contract to the said Contractor, such award being based on the acceptance by the City of the Contractor's bid;
ARTICLE II. That the City shall pay to the contractor for the performance of the work embraced in this contract and the contractor will accept as full compensation therefore the sum (subject to adjustment as provided by the contract) of
ARTICLE III. The contractor hereby agrees to act as agent for the City in purchasing materials and supplies for the City for incorporation into the work of this project. The City shall be obligated to the vendor of the materials and supplies for the purchase price, but the contractor shall handle all payments hereunder on behalf of the City. The vendor shall make demand or claim for payment of the purchase price from the City by submitting an invoice to the contractor. Title to all materials and supplies purchased hereunder shall vest in the City directly from the vendor. Regardless of the method of payment, title shall vest immediately in

Project No. 2012-CS-1.

the City. The contractor shall not acquire title to any materials and supplies incorporated into the project. All invoices shall bear the contractor's name as agent for the City. This paragraph will apply only to these materials and supplies actually incorporated into and becoming a part of the finished product of **Chip Seal**

CONTRACT AGREEMENT (Continued)

ARTICLE IV. That the contractor shall start work as soon as possible after the contract is signed and the required bond is approved and that the work in this contract shall be completed before **September 30, 2012**.

ARTICLE V. The Contractor agrees to comply with all applicable State fair labor standards in the execution of this contract as required by Section 73-102, R.R.S. 1943. The Contractor further agrees to comply with the provisions of Section 48-657, R.R.S. 1943, pertaining to contributions to the Unemployment Compensation Fund of the State of Nebraska. During the performance of this contract, the contractor and all subcontractors agree not to discriminate in hiring or any other employment practice on the basis of race, color, religion, sex, national origin, age or disability. The Contractor agrees to comply with all applicable Local, State and Federal rules and regulations.

ARTICLE VI. GRATUITIES AND KICKBACKS: City Code states that it is unethical for any person to offer, give, or agree to give any City employee or former City employee, or for any City employee or former City employee to solicit, demand, accept, or agree to accept from another person, a gratuity or an offer of employment in connection with any decision, approval, disapproval, recommendation, or preparation of any part of a program requirement or a purchase request, influencing the content of any specification or procurement standard, rendering of advice, investigation, auditing, or in any other advisory capacity in any proceeding or application, request for ruling, determination, claim or controversy, or other particular matter, pertaining to any program requirement or a contract or subcontract, or to any solicitation or proposal therefore. It shall be unethical for any payment, gratuity, or offer of employment to be made by or on behalf of a subcontractor under a contract to the prime contractor or higher tier subcontractor or any person associated therewith, as an inducement for the award of a subcontract to order.

ARTICLE VII. The City of Grand Island, Nebraska operates on a fiscal year beginning October 1st and ending on the following September 30th. It is understood and agreed that any portion of this agreement which will be performed in a future fiscal year is contingent upon the City Council adopting budget statements and appropriations sufficient to fund such performance.

ARTICLE VIII. FAIR EMPLOYMENT PRACTICES: Each proposer agrees that they will not discriminate against any employee or applicant for employment because of age, race, color, religious creed, ancestry, handicap, sex or political affiliation.

ARTICLE IX. LB 403: Every public consultant and his, her or its subconsultants who are awarded an agreement by the City for the physical performance of services within the State of Nebraska shall register with and use a federal immigration verification system to determine the work eligibility status of new employees physically performing services within the State of Nebraska.

IN WITNESS WHEREOF, the parties hereto have executed this Contract Agreement as of the date and year first above written.

CONTRACTOR

By	Date	
Title		
CITY OF GRAND ISLAND, NEBRASKA,		
ByMayor	Date	
Attest: City Clerk	_	
The contract and bond are in due form according to law a	and are hereby approved.	
	Date	
Attorney for the City		

APPENDIX A - TITLE VI NON-DISCRIMINATION -

During the performance of this contract, the contractor, for itself, its assignees and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- (1) Compliance with Regulations: The contractor shall comply with the Regulation relative to nondiscrimination in Federally-assisted programs of the Department of Transportation (hereinafter, "DOT") Title 49, Code of Federal Regulations, Part 21, and the Federal Highway Administration (hereinafter "FHWA") Title 23, Code of Federal Regulations, Part 200 as they may be amended from time to time, (hereinafter referred to as the Regulations), which are herein incorporated by reference and made a part of this contract.
- (2) Nondiscrimination: The Contractor, with regard to the work performed by it during the contract, shall not discriminate on the grounds of race, color, or national origin, sex, age, and disability/handicap in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor shall not participate either directly or indirectly in the discrimination prohibited by 49 CFR, section 21.5 of the Regulations, including employment practices when the contract covers a program set forth in Appendix B of the Regulations.
- (3) Solicitations for Subcontractors, Including Procurements of Materials and Equipment: In all solicitations either by competitive bidding or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials or leases of equipment, each potential subcontractor or supplier shall be notified by the contractor of the contractor's obligations under this contract and the Regulations relative to nondiscrimination on the grounds of race, color, or national origin, sex, age, and disability/handicap.
- (4) Information and Reports: The contractor shall provide all information and reports required by the Regulations or directives issued pursuant thereto, and shall permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the City of Grand Island or the FHWA to be pertinent to ascertain compliance with such Regulations, orders and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish this information the contractor shall so certify to the City of Grand Island, or the FHWA as appropriate, and shall set forth what efforts it has made to obtain the information.
- (5) Sanctions for Noncompliance: In the event of the contractor's noncompliance with the nondiscrimination provisions of this contract, the City of Grand Island shall impose such contract sanctions as it or the FHWA may determine to be appropriate, including, but not limited to:
 - (a.) withholding of payments to the contractor under the contract until the contractor complies, and/or
 - (b.) cancellation, termination or suspension of the contract, in whole or in part.
- (6) **Incorporation of Provisions:** The contractor shall include the provisions of paragraphs (1) through (6) in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Regulations, or directives issued pursuant thereto.

The contractor shall take such action with respect to any subcontract or procurement as the City of Grand Island or the FHWA may direct as a means of enforcing such provisions including sanctions for non-

compliance: Provided, however, that, in the event a contractor becomes involved in, or is threatened with, litigation with a subcontractor or supplier as a result of such direction, the contractor may request the City of Grand Island to enter into such litigation to protect the interests of the City of Grand Island, and, in addition, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

DIVISION I

GENERAL SPECIFICATIONS

APPLICABLE TO ALL CONSTRUCTION CONTRACTS

DIVISION I GENERAL SPECIFICATIONS

CONTENTS

Section	Description
1 1.01	DEFINITIONS OF WORDS AND TERMS Abbreviations
1.02	Advertisement
1.03	Award
1.04	Backslope
1.05	Bidder
1.06 1.07	Calendar Day
1.07	Change Order
1.09	City
1.10	Contract
1.11	Contract Items
1.12	Contract Region
1.13	Contract Period Contractor
1.14	Cul-de-sac Street
1.15	Culvert
1.16	Easement (Right-of-way)
1.17	Employee
1.18	Engineer
1.19	Extra Work
1.20	Holidays
1.21	Inspector
1.22	Laboratory
1.23	Notice to Bidders
1.24	Plans
1.25	Project
1.26	Bid
1.27	Bid Form
1.28	Bid Guarantee
1.29	Right-of-way
1.30	Special Provisions
1.31	Specifications
1,32	Subcontractor
1.33	Superintendent
1.34 1.35	Supplemental Agreements
1.36	Supplemental Specifications
1.37	Surety
1.38	Work
1.39	Working Drawin no
1.40	Working Drawings Work Order
1.41	
1.42	Completion of the Work and Formal Acceptance by the City
	Final Acceptance of the Work

Revised 1-25-2011

Section	Description
2	BID REQUIREMENTS AND CONDITIONS
2.01	Contents of Bid Forms
2.02	Interpretation of Quantities in Bid Forms
2.03	Examination of Plans, Specifications, Special
	Provisions and Site of Work
2.04	Preparation of Bid
2.05	Statement of Bidder's Plant and Financial Conditions
2.06	Certified, Check, Cashier's Check, or Bid Bond
2.07	Filing of Bid
2.08	Withdrawal of Bid
2.09	Public Opening of Bids
2.10	Material Guarantee
	AMARD AND EVECUTION OF THE CONTRACT
3.	AWARD AND EXECUTION OF THE CONTRACT
3.01	Consideration of Bids
3.02	Award of Contract
3.03	Cancellation of Award
3.04	Return of Bid Guarantee
3.05	Performance Bond
3.06	Contract Documents
	Revised 1-25-2011
3.07	Failure to Execute Contract
4	SCOPE OF WORK
4.01	Intent of Plans and Specifications
4.02	Special Work
4.03	Increased or Decreased Quantities of Work
	Revised 1-25-2011
4.04	Extra Work
4.05	Maintenance of Detours
4.06	Temporary Traffic Control
	Revised 1-25-2011
4.07	Maintenance of Traffic
4.08	Street Closing
4.09	Miscellaneous Removal Items
4.10	Removal and Replacement of Property Stakes
4.11	Removal and Disposal of Structures and Obstructions
4.12	Rights In and Use of Materials Found on the Right-of-Way
4.13	Construction and Demolition Debris
4.14	Final Cleaning Up
4.15	Right-of-way
4.16	Railroad Crossings
4.17	· · · · · · · · · · · · · · · · · · ·
7.17	Safety and Health Regulations for Constructions
5	CONTROL OF WORK
5.01	Authority of Engineer
5.02	Plans and Working Drawings
5.03	Alteration of Plans or of Character of Work
5.04	Coordination of Plans, Specifications, Special
	Provisions, and Supplemental Specifications
5.05	Cooperation of Contractor

Section	Description
5.06 5.07 5.08 5.09 5.10	Surveys Authority and Duties of Inspector Inspection of Work Removal of Defective Work Final Inspection
6 6.01 6.02 6.03 6.04 6.05 6.06	CONTROL OF MATERIALS Source of Supply and Quality Requirements Methods of Sampling and Testing, and Cited Specifications Storage of Materials Unacceptable Materials Guarantee "Or Equal" Clause
7	LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC
7.01 7.02 7.03 7.04 7.05 7.06 7.07 7.08 7.09 7.10 7.11 7.12 7.13	Laws to be Observed State and City Fair Labor Standards Anti-discrimination Permits Patents Restoration of Surface Opened by Permit Safety, Health, and Sanitation Barricades and Warning Signs Use of Explosives Claims for Labor and Materials Contractor's Insurance Proof of Carriage of Insurance Contractor's Responsibility for Utility Property and Services No Waiver of Legal Rights Exposure of Pipe or Manholes
8 8.01 8.02 8.03 8.04 8.05 8.06 8.07 8.08 8.09	PROSECUTION AND PROGRESS Subletting or Assigning of Contract Prosecution of Work Limitations of Operations Methods and Equipment Temporary Suspension of Work Liquidated Damages Extension of Contract Period Abrogation Termination of Contractor's Responsibility
9 9.01 9.02 9.03 9.04	MEASUREMENT AND PAYMENT Payments Payments Withheld Acceptance and Final Payment Payment for Extra Work

Revised 1-25-2011.

DIVISION I GENERAL SPECIFICATIONS

SECTION 1 - DEFINITIONS OF WORDS AND TERMS

Wherever in these specifications or in other contract documents the following terms or pronouns in place of them are used, the intent and meaning shall be interpreted as follows:

1.01	Abbreviations.				
	AASHTO	American Association of State Highway And			
	Transportation Officials				
	ASTM	American Society for Testing and Materials			
-	ANSI	American National Standards Institute			
	AWWA	American Water Works Association			
	AREA	American Railway Engineering Association			
	AWS	American Welding Society			
	AAN	American Association of Nurserymen			

- 1.02 <u>Advertisement</u>. The advertisement for work or materials on which bids are to be received.
- 1.03 <u>Award</u>. The decision of the City to accept the bid of the lowest responsible bidder for the work, subject to the execution and approval of a satisfactory contract therefor and bond to secure the performance thereof and to such other conditions as may be specified or otherwise required by law.
- 1.04 <u>Backslope</u>. The sloping surface of a cut, the downward inclination of which is toward the roadbed.
- 1.05 <u>Bidder</u>. Any individual, firm, or corporation formally submitting a bid for the work contemplated, acting directly or through a duly authorized representative.
- 1.06 <u>Calendar Day.</u> Every day shown on the calendar, Sundays and holidays included.
- 1.07 <u>Change Order.</u> A written order to the Contractor, signed by the Engineer, ordering a change in the work from that originally shown in the plans and specifications.
- 1.08 <u>City</u>. The word "City" as used in these specifications refers to the City of Grand Island, Nebraska, acting through its City Council.
- 1.09 <u>Contract</u>. The written agreement executed between the City and the Contractor, covering the performance of the work and the furnishing of labor and materials, by which the Contractor is bound to perform the work and furnish the labor and materials, and by which the City is obligated to compensate Contractor therefor at the mutually established and accepted rate or price.

The contract shall include the "Notice to Bidders", these specifications, the Contractor's bond, the general and detailed plans, the bid, special provisions, and supplemental agreements.

- 1.10 <u>Contract or Performance Bond.</u> The approved form of security, executed by the Contractor and their surety or sureties, guaranteeing complete execution of the contract and all supplemental agreements pertaining thereto and the payment of all legal debts pertaining to the construction of the project.
- 1.11 <u>Contract Item</u>. An item of work specifically described and for which a price, either unit or lump sum, is provided. It includes the performance of all work and the furnishing of all labor, equipment, and materials described in the text of a specification item included in the contract or described in any subdivision of the text of the supplemental specification or special provision of the contract.
- 1.12 <u>Contract Period</u>. The period from the date specified in the contract for the commencement of the work to the date specified for its completion, both dates inclusive.
- 1.13 <u>Contractor</u>. The party of the second part to the contract; the individual, firm, or corporation undertaking the execution of the work under the terms of the contract and acting directly or through Contractor's agents or authorized employees.
- 1.14 <u>Cul-de-sac Street</u>. A local street open at one end only and with special provision for turning around.
- 1.15 <u>Culvert</u>. Any structure not classified as a bridge which provides an opening under any street.
- 1.16 <u>Easement (Right-of-way)</u>. A right acquired by public authority to use or control property for a designated purpose.
- 1.17 <u>Employee</u>. Any person working on the project mentioned in the contract of which these specifications are a part, and who is under the direction or control or receives compensation from the Contractor or Contractor's subcontractor.
- 1.18 <u>Engineer</u>. The City Engineer, acting either directly or through an assistant or other representative duly authorized by the City Engineer, such assistant or representative acting within the scope of the particular duties assigned or with the authority given.
- 1.19 <u>Extra Work</u>. Work performed by the Contractor in order to complete the contract in an acceptable manner but for which there is no basis of payment provided in the contract.
- Holidays. In the State of Nebraska, holidays occur on: January 1, Martin Luther King, Jr. Day in January, Presidents' Day in February, Arbor Day in April, Memorial Day in May, July 4, Labor Day in September, Columbus Day in October, Veterans Day and Thanksgiving Day in November, and December 25. If any of said dates fall on Sunday, the following Monday shall be a holiday. If any of said dates fall on Saturday, the previous Friday shall be a holiday.
- 1.21 <u>Inspector</u>. An authorized representative of the Engineer assigned to make detailed inspection of any or all portions of the work performed and materials furnished by the Contractor.
- 1.22 <u>Laboratory</u>. The testing laboratory of the City or any other testing laboratory which may be designated by the Engineer.

- 1.23 <u>Notice to Bidders.</u> The provisions, requirements, and instructions pertaining to the work to be awarded, manner and time of submitting bids, quantities of the major items or work required, as prepared for the information of bidders.
- 1.24 <u>Plans</u>. The official plans, profiles, typical cross sections, general cross sections, working drawings, and supplemental drawings, or exact reproductions thereof, approved by the Engineer, which show the location, character, dimensions, and details of the work to be done, and which are to be considered as a part of the contract supplementary to these specifications.
- 1.25 Project. All work necessary to be performed under the contract.
- 1.26 <u>Bid.</u> The offer of the bidder, submitted on the prescribed bid form, to perform the work and to furnish the labor and materials at the prices quoted by the bidder.
- 1.27 Bid <u>Form</u>. The approved form on which the City requires formal bids be prepared and submitted.
- 1.28 Bid <u>Guarantee</u>. The security furnished by the Bidder with Bidder's bid for a project as a guarantee that Bidder will enter into a contract for the work if said bid is accepted.
- 1.29 <u>Right-of-way</u>. The land area which is reserved or secured by the City for constructing the work or for obtaining material therefor.
- 1.30 <u>Special Provisions</u>. Special directions, provisions, or requirements peculiar to the project under consideration and not otherwise thoroughly or satisfactorily detailed or set forth in the specifications.
- 1.31 <u>Specifications</u>. The general term comprising all the directions, provisions, and requirements contained herein, together with such as may be added or adopted as supplemental specifications or special provisions, all of which are necessary for the proper performance of the contract.
- 1.32 <u>Subcontractor.</u> Any individual, firm, or corporation to whom the Contractor, with the written consent of the City, sublets any part of the contract.
- 1.33 <u>Superintendent</u>. The representative of the Contractor, present on the work at all times during progress, authorized to receive and fulfill instructions from the Engineer and capable of superintending the work efficiently.
- 1.34 <u>Supplemental Agreements</u>. Written agreements executed by the Contractor and the City subsequent to having entered into the contract, covering alterations in the plans or unforeseen items of construction.
- 1.35 <u>Supplemental Specifications</u>. Specifications adopted subsequent to the publication of this book. They generally involve new construction items or substantial changes in the approved specifications. Supplemental specifications shall prevail over those published in this book whenever in conflict therewith.
- 1.36 <u>Surety</u>. The corporate body bound with and for the Contractor for the acceptable performance of the contract, the completion of the work, and for payment of all just claims arising therefrom.

- 1.37 <u>Work.</u> Work shall be understood to mean the furnishing of all labor, materials, equipment, and other incidentals necessary or convenient to the successful completion of the project by the Contractor and the carrying out of all the duties and obligations imposed by the contract.
- 1.38 <u>Working Day.</u> Any day, except Saturdays, Sundays, and Nebraska holidays, on which the Contractor is not prevented by weather, soil conditions, or other conditions beyond the Contractor's control, adverse to the current controlling operation or operations, as determined by the Engineer, from proceeding with at least 80 percent of the labor and equipment force normally engaged in such operation or operations for at least 50 percent of the full number of hours in Contractor's normal daily schedule. Also, a Saturday, Sunday, or Nebraska holiday on which any work is performed on the current controlling operation or operations unless the Contractor is prevented by weather, soil conditions, or other conditions beyond the Contractor's control as determined by the Engineer, from proceeding for at least 50 percent of the full number of hours in their normal schedule with 80 percent of the normal working force.
- 1.39 <u>Working Drawings</u>. Stress sheets, shop drawings, erection plans, falsework plans, framework plans, cofferdam plans, bending diagrams for reinforcing steel, or any other supplementary plans for similar data which the Contractor is required to submit to the Engineer for approval.
- 1.40 <u>Work Order.</u> A written order signed by the Engineer, of a contractual status requiring performance by the Contractor without negotiation of any sort and may involve starting, resuming, or the suspension of work. (Not to be confused with extra work order).
- 1.41 <u>Completion of the Work and Formal Acceptance by the City.</u> Whenever the term "completion of the work and formal acceptance by the City" is used, it refers to and means the formal acceptance of the work by the Engineer and the City at the time the Contractor has all work under the contract completed and in place.
- 1.42 <u>Final Acceptance of the Work.</u> Whenever the term "final acceptance of the work" is used, it refers to and means the time when the Engineer and the City finally accept the work. The contractor guarantee shall remain in force from the City's final acceptance for a period of one year.

Revised 1-25-2011

SECTION 2 – BID REQUIREMENTS AND CONDITIONS

- 2.01 <u>Contents of Bid Forms</u>. Bidders will be furnished with bid forms which will state the location and description of the contemplated work and will show the estimate of the various quantities and kinds of work to be performed or materials to be furnished, with a schedule of items for which unit bid prices are asked, the time in which the work must be completed and the date, time, and place of opening bids. All special provisions and required provisions will be grouped together and bound with or included through reference in the bid form.
- 2.02 <u>Interpretation of Quantities in Bid Forms</u>. The quantities listed in the bid forms are to be considered as approximate, unless otherwise provided by special provision. It is understood that the quantities of work to be done and materials to be furnished may each be increased, diminished, or omitted as hereinafter provided without in any way invalidating the unit bid prices, except as provided in the section in these specifications entitled Increased or Decreased Quantities of Work.

- 2.03 Examination of Plans, Specifications, Special Provisions, and Site of Work. The bidder is required to examine carefully the site, the bid, plans, specifications, special provisions, and contract form for the work contemplated, and it will be assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished and as to the requirements of these specifications, the special provisions, and contract. It is mutually agreed that the submission of a bid shall be considered prima facie evidence that the bidder has made such examination.
- 2.04 <u>Preparation of Bid.</u> Bidders shall submit their bids on blank forms furnished by the Engineer with the full name and address and the place of business or residence of the bidder. If the bidder is co-partnership, the signature shall be by a member of the firm with the names and addresses of each member. If the bidder is a corporation, the signature shall be by an officer of the corporation in the corporate name and with the corporate name and the corporate seal attached thereto.

All blank spaces in the form shall be fully filled; numbers shall be stated in legible figures and writing when required; the signature shall be longhand; and the complete form shall be without interlineation, alteration, or erasure.

No oral, telegraphic, or telephonic bids or modifications will be considered.

When certain alternative prices, for both increasing and decreasing the cost, are required, as called for in the bid sheet, it must be understood that all materials and workmanship required shall be the best of their respective kinds and in all cases shall correspond with similar work herein specified and, if accepted, the work shall be done under the general terms of the specifications.

- 2.05 <u>Statement of Bidder's Plant and Financial Conditions</u>. Each bidder may submit with bid and, in any event, the City may, after bids are opened and prior to award of contract, require any bidder to submit the following data:
- 1. A statement that the bidder maintains a permanent place of business and address thereof;
- 2. A statement of equipment which the bidder proposes to use on the project, together with a statement noting that equipment previously mentioned which the bidder owns and that which bidder does not own but is certain bidder will be able to rent or otherwise procure for use on the project;
- 3. A financial statement, duly sworn to in a form approved by the City, listing assets and liabilities;
- 4. Statement listing projects of similar nature which the bidder has constructed or in the construction of which the bidder was actively engaged in a responsible capacity. Any bidder may be required by the City to submit additional data to satisfy the City that such bidder is prepared to fulfill the contract if it is awarded to them.
- 2.06 <u>Certified Check, Cashier's Check, or Bid Bond</u>. Each bidder must submit with the bid a certified check, cashier's check, or bid bond in the amount of not less than five percent (5%) of the amount bid, drawn to the order of the City Treasurer, Grand Island, Nebraska, guaranteeing the execution of the contract and bond required within ten (10) days of the notification of award. Any certified check must be issued by a bank in the State of Nebraska.

2.07 <u>Filing of Bid.</u> Bidders shall submit bid data on items offered in the Bid by filling in one set of data sheets supplied by the Engineering Department. The bid sheets shall be filled out legibly in <u>black ink</u> to permit reproduction.

Bidder security, when required, shall be enclosed in a special envelope marked, "BIDDER SECURITY/BID FOR _______." The envelope shall contain only a cashier's check or bidder's bond. This special envelope shall be attached to a sealed envelope containing the bid, filled out specifications, descriptive information drawings, qualification list and any other bid materials. This second envelope shall be marked "BID FOR ______." Bids of an incomplete nature or subject to multiple interpretations may, at the option of the Purchaser, be rejected as being irregular.

All bids shall be filed with the City at the place designated in the Notice to Bidders, prior to the time advertised for the opening of bids.

- 2.08 <u>Withdrawal of Bid.</u> A bidder will be permitted to withdraw said bid unopened after it has been submitted, if bidder's request for withdrawal is made in writing and delivered personally by the bidder or bidders' authorized representative prior to the time specified for opening of bids.
- 2.09 <u>Public Opening of Bids.</u> Bids will be publicly opened and read at the time and place stipulated in the Notice to Bidders.
- 2.10 <u>Material Guarantee</u>. Before any contract is awarded, the bidder may be required to furnish a complete statement of the origin, composition, and manufacture of any or all materials to be used in the construction of the work together with samples, which samples may be subjected to the test provided for in these specifications to determine their quality and fitness for the work.

SECTION 3 - AWARD AND EXECUTION OF THE CONTRACT

3.01 <u>Consideration of Bids.</u> After the bids are opened and read, they will be compared on the basis of the summation of the products and the quantities shown in the bid schedule by the unit bid prices. The results of such comparisons will be immediately available to the public.

The right is reserved to reject any and all bids and to waive technical errors as may be deemed best for the interest of the City.

3.02 <u>Award of Contract</u>. In the award of contract, consideration will be given not only to the prices bid but also the mechanical and other equipment available to the bidder, the financial responsibility of the bidder, and bidder's ability and experience in the performance of like or similar contracts.

Award of contracts will be made as promptly as practical after bids have been opened and read. The City reserves the right to delay the award for such time as is needed for the consideration of the bids and for the receipt of concurrence in recommended contract awards from other governmental agencies whose concurrence may be required.

- 3.03 <u>Cancellation of Award</u>. The City reserves the right to cancel the award of any contract at any time before execution of the said contract by all parties without any liability against the City.
- 3.04 <u>Return of Bid Guarantee</u>. Bid guaranties will be returned to the unsuccessful bidders by mail promptly after the signing of the contract has been made. Return to the successful bidder will be made after the signing of the contract and filing of the contract bond.

3.05 <u>Performance Bond</u>. The Contractor shall furnish a performance bond with a company having the approval of the City in an amount of 100 percent of the contract price guaranteeing complete and faithful performance of the contract, payment of all bills of whatever nature which could become a lien against the property, and guaranteeing replacement of defective materials and workmanship for a period of one year after completion of the contract.

3.06 <u>Contract Documents</u>. Three (3) copies of Contract Documents shall be made, executed, and distributed as follows:

One copy to City Clerk

One copy to Contractor

One copy to Engineer

The following documents are a part of the contract:

*Notice to Bidders

*General Specifications

*Instructions to Bidders

*Special Provisions

*Bid

*Supplemental Specifications

*Detailed Specifications

*Performance Bond

*Contract

*Additional Drawings as required to make clear the intent of the contract

of the contract

Revised 1-25-2011

3.07 <u>Failure to Execute Contract</u>. Failure to execute a contract and file an acceptable performance bond as provided herein within ten (10) days from date of award shall be just cause for the annulment of the award and the forfeiture of the certified check or cashier's check to the City, not as a penalty but in liquidation of damages sustained.

SECTION 4 - SCOPE OF WORK

4.01 <u>Intent of Plans and Specifications</u>. The intent of the plans and specifications is to provide for the construction and completion of every detail of the work described therein. It shall be understood by the Contractor that Contractor will furnish all labor, materials, tools, transportation, and supplies required for all or any part of the work to make each item complete in accordance with the spirit of the contract. It is understood that the apparent silence of the specifications as to any detail or the apparent omission of a detailed description concerning any point shall be regarded as meaning that only the best general practice is to prevail and that only materials and workmanship of the first quality are to be used.

For the purpose of design and the preparation of the Engineer's Estimate, the City may perform a reasonable amount of exploratory work to gain information relative to surface and subsurface conditions relating to type of soil, moisture content, and types and extent of rock strata.

This information when shown on the plan represents to the best of the City's knowledge conditions as of the date the survey was made. The appearance of this information on the plan will not constitute a guarantee that conditions other than those indicated will not be encountered at the time of construction.

The bidder may utilize this information as they see fit. Any bidder interested in the work is authorized to make whatever investigation they considers advisable.

In making such additional investigation, the bidder is directed to the Engineer for information relating to available right-of-way. If there are, at that time, any parcels of land over which the City does not have jurisdiction, right of entry must be secured by the prospective bidder from those authorized to grant such permission. Investigational work, performed by a prospective bidder on existing streets open to traffic, shall be performed in compliance with the

requirements of the current Manual on Uniform Control Devices for Street and Highways. All such additional investigational work shall be performed without costing or obligating the City in any way.

- 4.02 <u>Special Work</u>. Any conditions not covered by these standard specifications are stated in the special provisions.
- 4.03 Increased or Decreased Quantities of Work. The Engineer reserves the right to alter the quantities of contract items for which there are bid prices. Such increases or decreases in quantities shall be made as the City considers necessary or desirable without waiving or invalidating any of the provisions of the contract. All such alterations must be ordered in writing and a supplemental agreement must be executed with the Contractor for the item or items involved when such alterations involve an increase or decrease of more than 20 percent of the total cost of the work of any group of the contract calculated from the original bid quantities and the contract unit prices. The Contractor shall not start work on any alteration requiring a supplemental agreement until the agreement setting forth an equitable adjustment of compensation, satisfactory to both parties, shall have been executed by the Engineer and the Contractor and approved by City Council.

Revised 1-25-2011

- 4.04 <u>Extra Work</u>. The City reserves the right to order the performance of work of a class not contemplated in the bid but which may be considered necessary to complete satisfactorily the work included in the contract. Such extra work will be paid for as provided in these specifications under section entitled Payment for Extra Work.
- 4.05 <u>Maintenance of Detours</u>. Unless so required by the plans or the special provisions, the Contractor will not be required to assume any responsibility in connection with the maintenance or marking of suitable detours.
- 4.06 <u>Temporary Traffic Control.</u> Part VI of the Manual of Uniform Traffic Control Devices (MUTCD) is the national standard for work zone traffic control. The current version that has been adopted by the Nebraska Department of Roads is also applicable to the City of Grand Island and shall be followed.

Any City crews, contractors, utility company, or any other person, firm or corporation performing work within the right-of-way of any public street, public way, or alley in the City of Grand Island shall install and maintain Temporary Traffic Control (TTC) in accordance with the standards of the MUTCD.

The Public Works Director or their representative shall have the authority to direct corrective actions for any TTC not in compliance with the MUTCD and these provisions. These actions may include suspending operations and requiring removal of all equipment or materials from the right-of-way.

If the TTC is left in place longer than four (4) hours and no personnel are on the site, the individual responsible for installing the TTC shall provide telephone numbers of personnel who will be available on a 24 hours per day, seven days per week basis to the Public Works Director. These individuals shall be responsible for repair, correction, replacement and maintenance of the traffic control devices. These individuals shall perform inspections of the TTC at the site a minimum of twice during the day and once during the night every day until the work is completed and the right-of-way is cleared.

Subsidiary: Unless contract pay items are included with the bid specifications, direct payment for providing, installing, maintaining, and performing site inspections of TTC devices will not be made but are considered subsidiary to other items for which direct payment is

provided. When the contract contains a pay item for TTC, the NDOR standard items, specifications, etc. will be used.

Revised 1-25-2011

- 4.07 <u>Maintenance of Traffic.</u> The Contractor shall conduct the work so as to interfere as little as possible with public travel, whether vehicular or pedestrian. Whenever it is necessary to cross, obstruct, or close roads, driveways, and walks, whether public or private, the Contractor shall, at Contractor's expense, provide and maintain suitable and safe bridges, detours, or other temporary expedients for the accommodation of public and private travel, and shall give reasonable notice to owners of private drives before interfering with them. Such maintenance of travel will not be required when the Contractor has obtained permission from the owner or tenant of private property or from the authority having jurisdiction over public property involved to obstruct traffic at the designated area.
- 4.08 <u>Street Closing</u>. In the event it is deemed necessary for the Contractor to close any streets during the execution of said work, the Contractor shall notify the owner of such street closing 72 hours in advance, prior to any street closing due to open cut street crossing.
- 4.09 <u>Miscellaneous Removal Items</u>. The Contractor shall inform the Engineer sufficiently ahead of construction so landowners can be notified to remove small trees, shrubs, and fences from the construction limits if the landowners desire to save them.
- 4.10 Removal and Replacement of Property Stakes. If it is necessary to remove any property corners or markers during construction operations, the Contractor shall notify the Engineer so the Engineer can establish reference ties. Any markers removed without notice to the Engineer shall be replaced at the Contractor's expense in accordance with the proper land surveying techniques.
- 4.11 Removal and Disposal of Structures and Obstructions. The Contractor for bridge and culvert work shall remove any existing structure or part of structure that in any way interferes with the new construction. If specific payment for such work has not been provided in the contract, it will be paid for as extra work.

The Contractor shall remove any materials or structures found on the right-of-way which are not to remain in place or which have not been designated for use in the new construction. The removal and disposal of pipe culverts will not be paid for directly but shall be considered as incidental work, and the cost of such removal and disposal shall be considered to be included in the contract price for other items. Pipe culverts shall be removed by methods that will cause a minimum of damage to the pipe culverts. The removal and disposal of bridges or other masonry or monolithic concrete construction will be paid for. If the contract does not contain an item for such work, it will be paid for as extra work.

Rights In and Use of Materials Found on the Right-of-way. Unless stated to the contrary in the contract documents, all materials, such as stone, gravel, sand, timber, and structures or parts of structures, found on the right-of-way of the street or on land acquired for the work, are the property of the City or the owner of the fee title to the land, and shall not be used or destroyed by the Contractor without special permission from the Engineer. When the Contractor is permitted to use materials found on the right-of-way, any excavations that they make below the grade elevation shall be backfilled with other suitable materials so the finished street will conform to the grade shown on the plans. No extra compensation will be allowed for such backfilling.

When rock excavation is encountered, any portion of rock excavation which would otherwise be deposited in waste areas and not be incorporated in the embankments may be processed and used, royalty free, by the Contractor in any other portion of the construction in which material of that quality would be acceptable. No deduction will be made from excavation quantities for rock so used.

- 4.13 <u>Construction and Demolition Debris.</u> Debris from any City awarded project, as well as Municipal Solid Waste (that is not recycled), shall be disposed of at the City's Solid Waste facilities.
- 4.14 <u>Final Cleaning Up.</u> Upon completion of the work and before acceptance and final payment, the Contractor shall clean the street, borrow pits, and all ground occupied by Contractor in connection with the work of all rubbish, excess materials, falsework, temporary structures, and equipment, and all parts of the work, shall be left in a neat and presentable condition.

When required in the plans, the Contractor shall, at Contractor's expense, replace waste material or stripping back into borrow and material pits as directed by the Engineer. Trees, tree stumps and material placed on property adjacent to the street during the execution of the work shall be disposed of by the Contractor.

- 4.15 <u>Right-of-way</u>. Right-of-way for the work will be provided without cost to the Contractor. Right-of-way will be made available to the Contractor on or before the date specified for the commencement of the work unless a later date for the right-of-way to be made available to the Contractor is designated in the contract documents.
- 4.16 <u>Railroad Crossings</u>. Whenever the work involves construction with which railroad companies are concerned, the performance of the work is contingent upon arrangements with the railroad companies for the proposed construction. No claims will be allowed for loss or damage caused by failure to complete such arrangements.
- Safety and Health Regulations for Construction. Occupational Safety and Health Standards for the Construction Industry (29 CFR Part 1926) with amendments as of February 1, 1999 promulgated by the Occupational Safety and Health Administration, United States Department of Labor, Washington, D.C. are incorporated herein as a part of the contract documents.

SECTION 5 - CONTROL OF WORK

- Authority of Engineer. The Engineer will have general supervision of the work and will decide any questions that arise with reference to the intent of the contract documents and compliance therewith. Said Engineer will relay all questions relating to materials, work, progress, disputes and mutual rights between contractors, fulfillment of contract, and compensation, in accordance with the provisions of these specifications.
- Plans and Working Drawings. The approved plans will be supplemented by such working drawings as are necessary to adequately control the work. It is mutually agreed that all authorized alterations affecting the requirements and information given in the approved plans shall be in writing.

Working drawings for any structure shall consist of such detailed plans as may be required of the Contractor for the prosecution of the work. These are not included in the plans

furnished by the Engineer. They shall include shop details, erection plans, masonry, and form work. The Engineer's prior approval of the shop details must be obtained before any fabrication work involving these plans is performed. Erection plans, masonry layout diagrams, and plans for cribs, cofferdams, falsework, centering, and form work, as well as any other working drawings not previously mentioned, may be required of the Contractor and shall be subject to the Engineer's approval.

No changes shall be made in any plan or drawing after it has been approved except by consent or direction of the Engineer in writing. It is expressly understood that the approval by the Engineer of the Contractor's working drawings will not relieve the Contractor from any responsibility.

The contract price shall include the cost of furnishing all working drawings, and the Contractor will be allowed no extra compensation for such drawings.

Shop plans shall be made on 22"x36" sheet with ½" margin on all sides except the left which shall be 2". The margin lines shall measure 21"x33 ½". The marking shall be in accordance with the special plans or as may be required by the Engineer. All blueprint plans which are furnished to the Engineer shall be clear and distinct and acceptable to the Engineer and shall be neatly trimmed. The Contractor shall furnish the Engineer as many extra copies of working drawings as the Engineer may direct.

The Engineer may require reproducible prints of all approved shop plans, which shall be furnished by the Contractor without cost to the Engineer. Such reproducible prints shall not be folded but shall be mailed in tubes sized to accommodate these plans without injuring them. No preliminary working drawings will be accepted by the Engineer unless they have been carefully checked by the Contractor. Drawings showing gross errors will be returned for recheck before examination by the Engineer. The name of the shop or company furnishing the drawings shall be on the tracing.

- 5.03 <u>Alteration of Plans or of Character of Work.</u> The Engineer shall have the right to make alterations in plans or character of work as may be considered necessary or desirable during the progress of the work to satisfactorily complete the proposed construction. Such alterations shall not be considered as a waiver of any conditions of the contract or invalidate any of the provisions thereof.
- Specifications. These specifications, the supplemental specifications, the plans, special provisions, and all supplementary documents are essential parts of the contract, and a requirement occurring in one is as binding as though occurring in all. They are intended to be complementary and to describe and provide for a complete work. In case of discrepancy, figured dimensions shall govern over scaled dimensions, plans shall govern over specifications, special plans shall govern over standard plans, supplemental specifications, supplemental specifications, and special provisions shall govern over specifications, supplemental specifications, and the plans.
- 5.05 <u>Cooperation of Contractor</u>. The Contractor will be supplied with a minimum of two sets of approved plans and contract assemblies, including special provisions, one set of which the Contractor shall keep available on the work at all times.

The Contractor shall give the work the constant attention necessary to facilitate the progress thereof and shall cooperate with the Engineer and other contractors in every way possible.

The Contractor shall at all times have at the work site, as Contractor's agent, a competent superintendent capable of reading and thoroughly understanding the plans and specifications, thoroughly experienced in the type of work being performed, who shall receive

instructions from the Engineer or Engineer's authorized representatives. The superintendent shall have full authority to execute the orders or directions of the Engineer without delay, and to promptly supply materials, equipment, tools, labor, and incidentals as may be required. Such superintendence shall be furnished irrespective of the amount of work sublet.

- 5.06 <u>Surveys</u>. Lines and elevations shall be established by the Engineer before the work commences and the Contractor shall obtain lines and elevations from the points so set by the Engineer. The Contractor shall furnish all stakes necessary for lines and elevations and cooperate with the Engineer in setting same.
- Authority and Duties of Inspector. The City may appoint inspectors to represent the Engineer in the inspection of all materials used in and all work done under the contract. Such inspection may extend to any part of the work and to the preparation or manufacture of the materials to be used. The inspector will not be permitted to modify in any way the provisions of the contract documents, nor to delay the work by failing to inspect materials and work with reasonable promptness. An inspector is placed at the work site to keep the Engineer informed as to its progress and the manner in which it is being done and to call the Contractor's attention to any infringements of the contract documents. The inspector will not act as foreman or perform other duties for the Contractor nor improperly interfere with the management of the work. They will not be authorized to approve or accept any portion of the work. In case of dispute between the Contractor and the inspector as to quality of materials or the manner of performing the work, the inspector shall have the authority to reject materials or suspend the work until the question at issue can be decided by the Engineer. Written notice of the suspension of work will be given to the Engineer and the Contractor.
- Inspection of Work. The Contractor shall furnish the Engineer with every reasonable facility for ascertaining whether the work is being performed in conformance with the contract documents. At any time before acceptance of the work, upon request of the Engineer, the Contractor shall remove or uncover such portions of the finished work as the Engineer may direct. After examination has been made, the Contractor shall restore such portions of the work to the standard required by the contract documents.

If the work thus exposed or examined proves acceptable, the uncovering or removing and replacing of the covering or the restoring of the parts removed shall be paid for as extra work, except that no payment will be made for the work involved in checking the smoothness of pavement surfaces. If the work thus exposed and examined proves unacceptable, the Contractor shall replace the defective work in accordance with the specifications and will be paid only the contract price for the work as finally accepted. Work done or materials used without the Engineer having been afforded ample opportunity to provide suitable inspection may be ordered removed and replaced at the Contractor's expense or may be excluded from the quantities measured for payment.

Removal of Defective Work. Any defective work shall be removed and replaced at the Contractor's expense. Should the Contractor fail or refuse to remove defective work when so ordered by the Engineer, the Engineer shall have authority to order the Contractor to suspend further operations and may withhold payment on estimates until such defective work has been removed and replaced in accordance with the plans and specifications. Continued failure or refusal on the part of the Contractor to correct defective work promptly shall be sufficient cause for the City to declare the contract in default and to proceed to have the work completed in accordance with these specifications under section entitled Abrogation.

5.10 <u>Final Inspection</u>. Upon notification by the Contractor or Contractor's authorized representative that the work is completed, the Engineer shall make prompt final inspection of each item of work included in the contract. If the work is found to not be in accordance with the contract documents, the Contractor will be advised as to the particular defects to be remedied.

SECTION 6 - CONTROL OF MATERIALS

6.01 <u>Source of Supply and Quality Requirements</u>. The materials used on the work shall meet all quality requirements of the contract. In order to expedite the inspection and testing of materials, the Contractor shall notify the Engineer of Contractor's proposed sources of materials prior to delivery. At the option of the Engineer, approval of the source or approval of materials at the source prior to delivery may be required. If it is found after trial that sources of supply for previously approved materials do not produce specified products or when conditions are such that the use of unfit materials cannot be prevented except by extraordinary inspection methods, the Contractor shall

furnish materials from other sources. Before delivery is started and at any time during the process of preparation and use, the materials shall be subject to the approval of the Engineer.

Methods of Sampling and Testing, and Cited Specifications. Sampling and testing of all materials and the laboratory methods and testing equipment required under these specifications shall be in accordance with the latest published standard method of the AASHTO, except as otherwise provided.

The sampling and testing of all materials not covered by the AASHTO, but not otherwise provided for, shall conform to the latest published standard or tentative methods of the ASTM.

- Storage of Materials. The Contractor shall be responsible for the care and storage of materials delivered at the work site or purchased for use thereon. Any material that has been delivered to the work site and has become damaged before actual incorporation in the work may be rejected by the Engineer even though it may previously have been accepted. Stored materials shall be so located as to facilitate thorough inspection.
- 6.04 <u>Unacceptable Materials</u>. All materials not conforming to the requirements of the specifications at the time they are to be used shall be considered as unacceptable, and all such materials will be rejected and shall be removed immediately from the site of the work unless otherwise instructed by the Engineer. No rejected materials, the defects of which have been corrected, shall be used until approval has been given.
- Guarantee. The Contractor shall be responsible for any and all defects which may develop in any part of the entire installation furnished by said Contractor and, upon receipt of written notice from the Engineer, shall immediately replace and make good without expense to the City any such faulty part or parts and damage done by reason of same during a period of one (1) year from the date of formal acceptance of the installation (except when specific guarantee for another length of time is elsewhere specified).

The acceptance of the installation, or any part of it, shall not act to waive this liability on the part of the Contractor.

Upon completion and formal acceptance of the work, the Contractor may furnish a satisfactory bond in an amount of fifteen percent (15%) of contract price to insure the provisions of this guarantee. Otherwise, the original bond shall remain in full force and effect until final acceptance of the work, which acceptance shall be made one (1) year after the formal acceptance of the work as provided herein.

6.06 "Or Equal" Clause. Whenever, in any section of the contract documents, plans, or specifications, any article, material, or equipment is defined by describing a proprietary product or by using the name of a manufacturer or vendor, the term "or approved equal", if not inserted, shall be implied. The specific article, material, or equipment mentioned shall be understood as indicating the type, function, minimum standard or design, efficiency, and quality desired and shall not be construed in such a manner as to exclude manufacturer's products of comparable quality, design, and efficiency. The Engineer shall determine the acceptability of articles, materials, or equipment proposed as equals.

SECTION 7 - LEGAL RELATIONS AND RESPONSIBILITY TO THE PUBLIC

- Laws to be Observed. The Contractor shall keep fully informed of and, at all times, shall observe and comply with all Federal and State laws, all local bylaws, ordinances, and regulations, and all orders and decrees of bodies or tribunals having any jurisdiction or authority which in any manner affect those engaged or employed on the project, or which in any way affect the project. The Contractor shall protect and indemnify the City and its representatives against any claim or liability arising from or based on the violation of any such law, ordinance, regulation, order, or decree, whether by said Contractor or Contractor's employees. It shall be the responsibility of the Contractor to provide all safeguards, safety devices, and protective equipment and to take any other needed actions as are reasonably necessary to protect the life and health of employees on the project.
- 7.02 <u>State and City Fair Labor Standards</u>. The Contractor agrees to comply with all applicable State and City fair labor standards in the execution of the contract, including compliance with Section 73-102, R.R.S. 1943. The Contractor further agrees to comply with the provisions of Section 48-657, R.R.S. 1943, pertaining to contributions to the Unemployment Compensation Fund of the State of Nebraska. In addition, the Contractor agrees to comply with the provisions of Section 52-118, R.R.S. 1948, pertaining to payment of all labor performed and for payment for materials and equipment rental which is actually used in performing this contract.
- 7.03 <u>Anti-discrimination</u>. During the performance of the work, the Contractor agrees not to discriminate against any employee or application for employment because of race, color, age, religion, sex, or national origin.
- 7.04 <u>Permits.</u> The Contractor shall procure and pay for all permits, licenses, and bonds necessary for the prosecution of Contractor's work and/or required for municipal, State, and Federal regulations and laws.
- 7.05 <u>Patents</u>. The Contractor and the surety in all cases shall indemnify and save harmless the City for any costs, expenses, and damages which it may be obligated to pay by reason of any such infringement at any time during the prosecution of or after the completion of the project.
- Restoration of Surfaces Opened by Permit. Upon the presentation of a duly authorized and satisfactory permit from the City which provides that all necessary repair work will be paid for by the party to whom such permit is issued, the Engineer may authorize the Contractor to allow parties bearing such permits to make openings in the street. The Contractor shall, when ordered by the Engineer in writing, make in an acceptable manner all necessary repairs due to such openings, and such necessary work ordered by the Engineer shall be paid for on the basis of "Extra Work" as provided for in these specifications and shall be subject to the same conditions as original work performed.

- 7.07 <u>Safety, Health, and Sanitation.</u> In the performance of the contract, the Contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation. The Contractor shall furnish such additional safeguards, safety devices, and protective equipment and shall take actions as the Engineer may determine as being reasonably necessary to protect the life and health of Contractor's employees and the public.
- 7.08 <u>Barricades and Warning Signs</u>. Except as otherwise provided specifically in this section, the Contractor shall provide and maintain barricades, danger and warning signs, and suitable and efficient lights, and shall take every reasonable precaution to prevent accidents. The name of the Contractor shall be clearly visible on the barricades. The Contractor shall provide, at their own expense, such watchmen as are necessary to protect their equipment and to maintain proper lights.

Watchmen who may be necessary to direct traffic or prevent travel on any portion of the street shall be provided by the Contractor on written order from the Engineer. Unless the contract specifically provides that such watchmen are to be furnished by the Contractor, this expense shall be paid for as provided in "Extra Work."

- 7.09 <u>Use of Explosives</u>. When the use of explosives is necessary for the prosecution of the work, the Contractor shall use the utmost care not to endanger life or property. All explosives shall be stored in a secure manner, and storage places shall be clearly marked "DANGER-EXPLOSIVES."
- Claims for Labor and Materials. The Contractor shall indemnify and save harmless the City from all claims for labor and materials furnished under this contract. When requested by the City, the Contractor shall submit satisfactory evidence that all persons, firms, or corporations who have done work or furnished materials under this contract, for which the City may become liable under the laws of the State, have been fully paid or satisfactorily secured. In case such evidence is not furnished or is not satisfactory, an amount will be retained from money due the Contractor which, in addition to any other sums that may be retained, will be sufficient, in the opinion of the City, to meet all claims of the persons, firms, and corporations as aforesaid. Such sum shall be retained until the liabilities as aforesaid are fully discharged or satisfactorily secured.
- Contractor's Insurance. The Contractor shall secure and maintain throughout the duration of this contract insurance, from companies authorized to do business in Nebraska, of such types and in such amounts as may be necessary to protect themselves and the interests of the City against all hazards or risks of loss as hereinafter specified. This insurance shall cover all aspects of the Contractor's operations and completed operations. The form and limits of such insurance, together with the underwriter thereof in each case, shall be approved by the City, but regardless of such approval it shall be the responsibility of the Contractor to maintain adequate insurance coverage at all times. Failure of the Contractor to maintain adequate coverage shall not relieve them of any contractual responsibility or obligation. Minimum insurance coverage shall be the amounts stated herein or the amounts required by applicable law, whichever are greater.
- 1. "Worker's Compensation and Employer's Liability." This insurance shall protect the Contractor against all claims under applicable State worker's compensation laws. This insurance shall provide coverage in every state in which work for this project might be conducted. The Contractor shall also be protected against claims for injury, disease, or death of employees which, for any reason, may not fall within the provisions of a worker's compensation

law. This policy shall include an "all states" endorsement. The liability limits shall be not less than the following:

Worker's Compensation Employer's Liability Statutory Limits \$100,000 each accident \$100,000 each employee \$500,000 policy limit

2. "Business Automobile Liability." This insurance shall be written in comprehensive form and shall protect the Contractor, Contractor's employees, or subcontractors from claims due to the ownership, maintenance, or use of a motor vehicle. The liability limits shall be not less than the following:

Bodily Injury & Property Damage \$50

\$500,000 Combined Single Limit

3. "Comprehensive General Liability." The comprehensive general liability coverage shall contain no exclusion relative to explosion, collapse, or underground property. The liability limits shall be not less than the following:

Bodily Injury & Property Damage \$ 500,000 each occurrence \$1,000,000 aggregate

4. "Umbrella Liability Insurance." This insurance shall protect the Contractor against claims in excess of the limits provided under employer's liability, comprehensive automobile liability, and commercial general liability policies. The umbrella policy shall follow the form of the primary insurance, including the application of the primary limits. The liability limits shall not be less than the following:

Bodily Injury & Property Damage

\$1,000,000 each occurrence \$1,000,000 general aggregate

5. Additional Requirements. The City may require insurance covering a Contractor or Subcontractor more or less than the standard requirements set forth herein depending upon the character and extent of the work to be performed by such Contractor or Subcontractor.

Insurance as herein required shall be maintained in force until the City releases the Contractor of all obligations under the contract.

The Contractor shall provide and carry any additional insurance as may be required by special provisions of these specifications.

6. Certificate of Insurance. Satisfactory certificates of insurance shall be filed with the City prior to starting any work on this contract. The certificates shall show the City as an additional insured on all coverage except Workers Compensation. The certificate shall state that thirty (30) days written notice shall be given to the City before any policy is cancelled (strike the "endeavor to" wording often shown on certificate forms). If the Contractor cannot have the "endeavor to" language stricken, the Contractor may elect to provide a new certificate of insurance every thirty (30) days during the contract. The Contractor shall immediately notify the City if there is any reduction of coverage because of revised limits or claims paid which affect the aggregate of any policy.

- 7.12 <u>Proof of Carriage of Insurance</u>. Satisfactory certificates of insurance shall be filed with the City prior to starting any construction work on this contract. The certificates shall show the City as "Additionally Insured." The certificates shall state that thirty (30) days written notice shall be given to the City before any policy covered thereby is changed or canceled (strike the "endeavor to" wording often shown on certificate forms).
- 7.13 Contractor's Responsibility for Utility Property and Services. At points where the Contractor's operations are adjacent to properties of railway, telegraph, telephone, and power companies or adjacent to other property to which damage might result, work shall not be commenced until all arrangements necessary for the protection thereof have been made.

The Contractor shall cooperate with the owners of any underground or overhead utility lines in their removal and rearrangement operations in order that these operations may progress in a reasonable manner, that duplication of rearrangement work may be reduced to a minimum, and that services rendered by those parties will not be unnecessarily interrupted.

In the event of interruption to water or utility services as a result of accidental breakage or as result of being exposed or unsupported, the Contractor shall promptly notify the proper authority. Contractor shall cooperate with said authority in the restoration of service as promptly as possible. In no case shall interruption to water service be allowed to exist outside of working hours. Fire hydrants shall be kept accessible to the Fire Department at all times and no materials shall be kept or stockpiled within fifteen (15) feet of any fire hydrant.

The Contractor must cooperate with the utility companies and schedule work in such a manner as to protect the existing utility facilities until the facilities are abandoned or replacement facilities are completed. In instances where partial grading is necessary before a utility can install its facilities, the Contractor shall consult with the utility and plan the work so reasonable time can be allowed the utility for completing its work.

- No Waiver of Legal Rights. The City shall not be precluded or estopped by any measurement, estimate, or certificate made either before or after the completion and acceptance of the work and payment therefor from showing the true amount and character of the work performed and materials furnished by the Contractor, nor from showing that such measurement, estimate, or certificate is untrue or is incorrectly made, nor that the work or materials do not in fact conform to the contract. The City shall not be precluded or estopped, notwithstanding any such measurement, estimate, or certificate and payment in accordance therewith, from recovering from the Contractor or Contractor's sureties, or both, such damage as it may sustain by reason of Contractor's failure to comply with the terms of the contract. Neither the acceptance by the City or any representative of the City, nor any payment for or acceptance of the whole or any part of the work, nor any extension of time, nor any possession taken by the City shall operate as a waiver of any portion of the contract or of any power herein reserved or of any right to damages. A waiver of any breach of the contract shall not be held to be a waiver of any other or subsequent breach.
- 7.15 Exposure of Pipe or Manholes. The Contractor shall conduct the work at all times in such a manner as will insure no disruption to the normal function of the sanitary sewer collection system. Particular attention shall be paid to the threat of introduction of storm water or other waters to the piping and manholes of the collection system. The Contractor shall take whatever precautions are necessary, such as, but not limited to installation of plugs in exposed pipes and manholes when work is not in progress or when leaving the work site. The Contractor will be held responsible for damages which may occur to either the collection system or to private property through introduction of storm water or other waters to exposed piping or manholes relating to the construction work.

SECTION 8 - PROSECUTION AND PROGRESS

- 8.01 <u>Subletting or Assigning of Contract</u>. The Contractor will not be permitted to sublet, assign, sell, transfer, or otherwise dispose of the contract or any portion thereof or Contractor's right, title, or interest therein or to either legally or equitably assign any of the money payable under Contractor's contract or claim thereto without the written consent of Contractor's surety and the Engineer. The Contractor will not be relieved of any responsibility through any of the above actions.
- 8.02 <u>Prosecution of Work.</u> The bid for each project will show the contract period. The progress of the work shall be at a rate sufficient to complete the contract within the contract period. If it appears that the rate of progress is such that the contract will not be completed within the contract period or if the work is not being executed in a satisfactory and workmanlike manner, the City may order the Contractor to take such steps as it considers necessary to complete the contract within the period of time specified or to prosecute the work in a satisfactory manner. If the Contractor fails to comply with such order within two (2) weeks after receipt of the order, Contractor shall automatically be disqualified from receiving any additional contract awards, and the City shall have the right to declare the contract in default and to complete the work in accordance with these specifications under section entitled Abrogation.

The Contractor's sequence of operations shall be such as to cause as little inconvenience to the general public as possible.

The Contractor will be granted additional and suitable time for the prosecution of the work, as was lost by reason of a delay or delays attributable to other parties authorized to do work on the project over which the Contractor had no control or jurisdiction, as provided in these specifications under section entitled Extension of Contract Period.

- 8.03 <u>Limitations of Operations</u>. The Contractor shall conduct the work at all times in such a manner and in such sequence as will insure the least interference with traffic. Contractor shall have due regard to the location of detours and to the provisions of handling traffic. Contractor shall not open up work to the prejudice of work already started, and the Engineer may require the Contractor to finish a section on which work is in progress before work is started on any additional section. The Contractor shall so conduct operations and maintain the work in such condition that adequate drainage shall be in effect at all times.
- 8.04 <u>Methods and Equipment</u>. The methods, equipment, and appliances used shall produce a satisfactory quality of work and shall be adequate to maintain the schedule of progress specified. Equipment used on any portion of the project shall be such that no injury to the roadway, adjacent property, or other streets will result from its use.

When the methods and equipment to be used by the Contractor in accomplishing the construction are not prescribed in the contract, the Contractor is free to use any methods or equipment that is demonstrated to accomplish the contract work in conformity with the requirements of the contract to the satisfaction of the Engineer.

When the contract specifies that the construction be performed by the use of certain methods and equipment, such methods and equipment shall be used unless others are authorized by the Engineer. If the Contractor desires to use a method or type of equipment other than those specified in the contract, a request may be made to the Engineer for authority to do so. The request shall be in writing and shall include a full description of the methods and equipment proposed to be used and an explanation of the reasons for desiring to make the change. If approval is given, it will be on the condition that the contractor will be fully responsible for producing construction work in conformity with contract requirements. If, after trial use of the substituted methods or equipment, the Engineer determines that the work produced does not

meet contract requirements, the Contractor shall discontinue the use of the substitute method or equipment and shall complete the remaining construction with the specified methods and equipment. The Contractor shall remove the deficient work and replace it with work of specified quality or take such other corrective action as the Engineer may direct. No change will be made in basis of payment for the construction items involved nor in contract time as result of authorizing a change in methods or equipment under these provisions.

8.05 Temporary Suspension of Work. Work shall be suspended wholly or in part when, in the opinion of the Engineer, weather or other conditions are unfavorable to its satisfactory prosecution. Work shall also be suspended at the direction of the Engineer pending settlement of disputes arising out of failure of the Contractor to comply with the provisions of the contract. Written notice of suspension of work shall be given by the Engineer. When the conditions causing suspension no longer exist, such written notice shall be given to the Contractor by the Engineer. Promptly after such written notice, the Contractor shall resume prosecution of the work as provided in these specifications under section entitled Prosecution of Work.

8.06 <u>Liquidated Damages</u>. Time is an essential element of the contract, and it is important that the work be pressed vigorously to completion.

For each calendar day that any work shall remain uncompleted after the end of the contract period, the amount per calendar day specified in the bid form will be assessed, not as a penalty but as predetermined and agreed liquidated damages. The City will prepare and forward to the Contractor an invoice for such liquidated damages. The final payment will be withheld until payment shall have been made of this invoice.

Due account shall be taken of any adjustment of the contract period granted under the section of these specifications entitled Extension of Contract Period.

The assessment of liquidated damages for failure to complete the work within the contract period shall not constitute a waiver of the City's right to collect any additional damages which the City may sustain by failure of the Contractor to carry out the terms of the contract.

- 8.07 <u>Extension of Contract Period</u>. An extension of the contract period may be granted by the City for any of the following reasons:
 - 1. Additional work resulting from a modification of the plans for the project
 - 2. Delays caused by the City
- 3. Other reasons beyond the control of the Contractor which, in the City's judgment, would justify such extension.

No extension of contract period will be allowed for variations between contract quantities and actual quantities which cannot be predetermined and which amount to less than twenty percent (20%) of the contract quantities.

8.08 <u>Abrogation</u>. If the Contractor abandons, sublets, or assigns the work under this contract without the consent of the City, or if Contractor fails to give - personal attention to it, or if it is the Engineer's opinion, and is so certified in writing to the Contractor and the City, that the Contractor is violating any of the provisions of this contract or that Contractor is not prosecuting the work in good faith or at the rate of progress specified, or that Contractor has unnecessarily or unreasonably delayed or neglected the work or any part of it, written notice to that effect is to be given to the Contractor by the Engineer. After such notice, no materials or equipment shall be removed from the work. If, within five (5) days thereafter, the Contractor does not take steps, which in the judgment of the Engineer will insure the satisfactory completion of the work, then the City may declare this contract null and void and the security forfeited and may notify the Contractor in writing to discontinue the work or any part of it; thereupon ceasing the Contractor's right of possession of the ground and of all materials and equipment thereon. The City then, at

their option, may enter upon and take possession of the work with all materials, supplies, and equipment remaining thereon and by contract or otherwise, as the City may determine, may complete the work or the part of it designated and charge the expense thereof to the Contractor using any materials or equipment found on the site. The expense so charged, together with all damages incurred, will be deducted from any funds due or to become due under this contract and, should the unexpended balance of these funds be insufficient, the excess shall be at the cost of the Contractor and sureties on the Contractor's bond. Neither completion of a part of the work nor the extension for any reason of the time of the completion of the work is to be considered a waiver of this right to abrogate the contract for abandonment, delay, or unsatisfactory work.

8.09 <u>Termination of Contractor's Responsibility</u>. The contract shall be considered completed when the work has been accepted in writing by the City. Such acceptance shall release the Contractor from all further obligation with respect thereto, except as to conditions and requirement set forth in Contractor's bond.

SECTION 9 - MEASUREMENT AND PAYMENT

9.01 Payments. Payments for estimated work completed will be made only on certificates of the Engineer at a regular City Council meeting.

The City, at its discretion, may include in such estimates payments for materials that will eventually be incorporated in the project, provided that such materials are suitably stored on the site of the project at the time of preparing estimates for payment. Such payment is to be based upon the estimated value thereof as ascertained by the Engineer. Such material when so paid for by the City shall not be removed from the project without consent of the City and, in case of default on the part of the Contractor; the City may use or cause to be used by others these materials in construction of the project.

The City will retain five percent (5%) of the estimated amount of work executed in an approved manner and of the approved materials and apparatus suitably stored on the site.

Payment of the retained five percent (5%) will be made within sixty (60) days after the formal approval and acceptance by the Engineer of all apparatus, materials, and work embraced in the contract.

- 9.02 <u>Payments Withheld</u>. The City may withhold or, on account of subsequently discovered evidence, nullify the whole or a part of any certificate to such extent as may be necessary to protect itself from loss on account of:
 - Defective work not remedied
 - 2. Claims filed or reasonable evidence indicating probable filing of claims
 - Failure of the Contractor to make payments properly to subcontractors or for materials or labor
 - 4. A reasonable doubt that the contract can be completed for the balance then unpaid
 - 5. Damage to another contractor.

When the above grounds are removed, payment shall be made for amounts withheld because of them.

9.03 Acceptance and Final Payment. If final inspection reveals that all details of the work have been completed satisfactorily, the Engineer shall tentatively accept the work, in writing, relieving the Contractor of further responsibility for the care and maintenance of the completed work and, provided that all equipment and materials have been removed from the right-of-way, shall also relieve the Contractor of further public liability. As soon as possible after tentative


acceptance of the work, the Engineer shall measure the completed work and compute the quantities of work for which payment is to be made. Before final settlement is made, the City shall be satisfied with the completed work. When the Engineer is satisfied that all items of the work have been found to be consistent with the terms of the contract and specifications, a final estimate including the retained percentage due the Contractor shall be released for payment. Release of the final estimate shall constitute final acceptance of the work.

All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

Extra work - See these specifications under section entitled Extra Work.

- 9.04 <u>Payment for Extra Work</u>. The Contractor will receive and accept payment for work performed under the contract as follows:
- 1. Items of work performed which are covered by definite prices stipulated in the contract. For all items of work performed which are covered by definite unit prices or lump sum amounts specified in the contract, the Contractor shall receive and accept compensation at the rate specified in the contract.
- 2. Extra work ordered by the Engineer, of a quality or class not covered by the contract, will be paid for at an agreed price. For extra work ordered by the Engineer and performed on an agreed price basis, the Engineer and the Contractor shall enter into a written agreement, and have City Council approval, before such work is undertaken. This written agreement shall describe the extra work that is to be done and shall specify the agreed price or prices therefore.

Revised 1-25-2011



CHIP SEAL PROJECT 2012-CS-1

DIVISION IA - SPECIAL PROVISIONS

SECTION 200 - GENERAL

200.01 General Description of Work. Chip Seal is the sprayed application of asphaltic material with a covering of aggregate at the locations shown in the plans or as directed by the Engineer. The work to be performed under the terms of this contract consists of furnishing all materials, equipment, tools, labor and plant necessary to perform Chip Seal and other related work as shown on the plans.

The bid shall reflect a grand total for the entire program. The City may add or delete up to 25% of the contract dollar value based upon estimated quantities and bid unit prices without adjustment of unit prices. Pay requests shall reflect sub-totals for each section. Pay request sheets shall be supplied by the City.

200.02 Location of Work.

Section #1.

Shall be on bituminous surfacing on 4th Street east of Congdon Avenue to East 7th Street and on Sky Park Road from East 7th Street to East Capital Avenue.

<u>Traffic Control</u> – The Contractor may maintain traffic by flagging or close the street to through traffic. Access shall be made available to residents and businesses along 4th Street and Sky Park Road.

<u>Public Accommodation</u> – The contractor shall provide notice to impacted businesses and residents at least two weeks and 48 hours prior to starting work. The Contractor shall provide notice to Public Works at 308-385-5444, extension 260, at least two weeks and 48 hours prior to starting work.

Section #2.

Shall be on the Portland cement concrete surfacing on Broadwell Avenue from the north entrance to the Veteran's Fields Sports Complex north through the intersection of Airport Road.

<u>Traffic Control</u> – The Contractor may maintain traffic by flagging. Broadwell Avenue can be closed to through traffic from the entrance to Veteran's Field Sports Complex to south of the intersection of Airport Road. US-281 traffic will be detoured while work occurs at the intersection of Airport Road. Access shall be made available to Eagle Scout Park at all times except for short durations for work occurring immediately at the driveway.

Eastbound and westbound traffic must be maintained at Airport Road at all times.

<u>Public Accommodation</u> – The contractor shall provide notice to impacted businesses and residents at least two weeks and 48 hours prior to starting work. The Contractor shall provide notice to Public Works at 308-385-5444, extension 260, at least two weeks and 48 hours prior to starting work.

200.03 Specifications. The specifications which govern the materials and equipment to be furnished and the work to be performed under this contract are listed herein and in Division 1 – General Provisions and Division IA – Special Provisions. If there is information described in Division 1 that is in conflict with information in Division IA – Special Provisions, the information in the Special Provisions shall govern the contract.

200.04 <u>Liquidated Damages.</u> The Contractor shall perform the work within the period of time stipulated in the Contract Agreement, unless an extension of time is granted by the City Council. Liquidated damages shall be assessed per working day as per the formula shown in the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 108.08; Paragraph 2.

200.05 <u>Schedule.</u> (Schedule of Operations) The Contractor shall present a detailed schedule at the Pre-Construction meeting.

200.06 Completion. The work shall be completed before September 30, 2012.

200.07 Contractor's Insurance. In addition to the insurance required under Division I, Section 7.11, Contractor's Insurance, the insurance policy shall include completed operations coverage.

200.08 <u>Manholes.</u> Manhole rings and covers shall be protected in such manner that no asphaltic materials will adhere and prevent covers to be easily removed. This work is subsidiary to other items of work for which direct payment is made.

200.09 <u>Mobilization.</u> This work shall consist of preparatory work and operations, including, but not limited to, those necessary for the movement of personnel, equipment, supplies, and incidentals to the project site; and for all other work and operations which must be performed or costs incurred before beginning work at the project site.

The Contractor must include all costs that he/she expects to incur for all movements of his/her equipment and personnel. Additional payments will not be made should the Contractor elect to move his/her equipment and/or crew to another project site before the contracted work is complete or if the Contractor fails to adequately assess the actual cost of Mobilization for the contracted work.

SECTION 201 - CHIP SEAL

MATERIAL REQUIREMENTS

- 1. Chip Seal asphaltic material shall be the type and grade shown in the plans and shall conform to the following requirements.
- 2. Aggregate for Chip Seal shall be Expanded Shale and conform to the requirements of Subsection 1033.02, Paragraphs 1., 2., and 6.a. and 6.b of the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction. Aggregate shall meet the requirements of the following table.

GRADATION FOR EXPANDED SHALE 1/8" x 0 (Chip Seal)

	PERCENT	PERCENT PASSING		
SIEVE	MINIMUM	MAXIMUM		
#4	95	100		
#8	70	100		
#16	45	90		
#30	15	65		
#50	5	30		
#100	0	10		

3. Chip Seal Asphaltic Material shall be CRS-2P or CRS-2VHL. Asphaltic Materials shall be provided by a Supplier certified to provide Chip Seal Asphaltic Material for Nebraska Department of Roads Construction projects and Maintenance contracts.

CRS-2P shall meet the specifications of AASHTO M-316 with the following changes:

Penetration, 25°C (77°F), 100g, 5 sec	100-150
Ductility, 25°C (77°F), 5 cm/min	Min 40cm
Elastic Recovery (77°F), 5 cm/min	Min 55%
	See note "b" of AASHTO M 208
Sieve Test	See note "b" of AASHTO M 208
Force Ratio Test	Not Required
man	

Evaporation residue
Distillation will be used for residue percentage determination and all residue
testing. The distillation will be taken to 350± 5°F, and held for 20 minutes

and otherwise in accordance with AASHTO T 59.

Paragraph 3.1 of AASHTO M-316 is void and superseded by the following:

3.1 CRS-2P - A cationic emulsion made with base asphalt binder modified with styrene-butadiene or styrene-butadiene styrene block copolymers. All base stock asphalt used must be modified before emulsification. CRS-2P shall contain no latex polymer.

CRS-2VHL shall meet the following specifications:

Tests on Emulsion:	
Viscosity, Saybolt-Furol, 50°C (122°F), sec.	75 – 300
Residue by Distillation, % min., note 1	65
Oil Distillate, % by Volume, max.	3
Storage Stability, %, max.	1
Demulsibility, 35 ml of 0.8% C ₂₀ H ₃₇ NaO ₇ S, % min.	40
Sieve Test, % Retained, max., note 2	0.10
Particle Charge	Positive
Tests on Distillation Residue:	
Penetration, dmm, 25°C (77°F), 100 g., 5 sec.	65 – 130
Ductility, 77°F, cm., minimum	40
Softening Point, °F, min.	135

- Note 1: The distillation shall be taken to 350 +/- 5°F, and held for 20 minutes, and otherwise in accordance with AASHTO T 59.
- Note 2: Test requirement is waived if successful application of the material has been achieved in the field.

The solubility of the base asphalt binder shall be greater than 99.0%.

All polymer shall be added as either SBR or polychloroprene latex only, and only during a co-milling emulsification process. The latex polymer solids content shall be 3.0% minimum.

CONSTRUCTION METHODS

- 1. The Contractor shall furnish and place the Chip Seal as indicated in the plans.
- 2. Emulsified asphaltic material shall be applied at a minimum temperature of 160°F(71°C). The rate of application shall be 0.28 to 0.32 gallons per square yard, or as approved by the Engineer.
- 3. The surface shall be prepared as prescribed in Section 501 of the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction.
- 4. Chip Seal Application:
 - (1) The Contractor shall demonstrate the ability to distribute a uniform coat of a. asphaltic material before beginning work. A coat of the specified asphaltic material shall be applied to a test strip of tar paper or other suitable material. The strip shall be 10 feet (3 m) long and as wide as the spray bar. If the Engineer determines the application to be unsatisfactory, the Contractor will be required to adjust the equipment and repeat the test procedure until satisfactory results are obtained. The Contractor shall properly dispose of the test strip after use. Seamless transverse joints shall be obtained by placing 15 pound tar paper at the joint at the beginning and end of each shot. This should ensure that the correct rate of application is achieved for the full length of the shot and avoid double application of binder. The binder application shall commence with a running start on a strip of tar paper. The spray bar needs to be stopped on the tar paper at the end of each shot to ensure a straight transverse construction joint. Transverse joints shall have no more than 0.25 inch (6.5 mm) difference in elevation across the joint as measured with a 6 foot (2m) straightedge. The Chip Seal edge shall be neat and uniform along the roadway lane, shoulder and curb lines. The Chip Seal edge shall have no more than 2 inches (50mm) variance in any 100 foot (30m) section, along the roadway edge or shoulder.
 - (2) Aggregates shall be field sampled and tested for gradation by City personnel for each 200 cubic yards used.
 - (3) Special care shall be taken to secure an overlap of adjoining longitudinal applications.
 - (4) Hand sprayers shall be used in applying asphaltic materials to small or irregular sections.

- b. The cover aggregate shall be applied immediately (within 1 minute) after the application of the asphaltic material. The rate of application shall be 12 to 15 pounds of aggregate per square yard, or as approved by the Engineer.
- c. The application of asphaltic materials shall be allowed only when:
 - (1) The ambient temperature is above 60°F (16°C).
 - (2) The surface is dry. The Engineer may allow the application of emulsified asphalt to a damp surface if all standing water has been removed from the surface with squeegees and no further precipitation is expected.
- d. (1) The Contractor shall conduct the operations to minimize construction traffic on completed portions of the Chip Seal. Chip Seal equipment will not be allowed to travel on uncovered asphaltic materials.
 - (2) Application widths shall coincide with existing traffic lane lines to the maximum extent possible. The Chip Seal shall be applied to one-half of the width of the surface at a time, confining traffic to the portion of the surface not being treated.
 - (3) When Chip Seal is required on both roadway and surfaced shoulders, Chip Seal materials shall be applied to the shoulder's full width before Chip Seal materials are applied on any section of the adjacent traffic lane. Application widths shall coincide with lane and shoulder widths.
 - (4) Traffic will not be allowed on the completed Chip Seal until the aggregate is well embedded in the bituminous material.
- e. The moisture content of mineral aggregate for Chip Seal, at the time of application, shall be satisfactory to the Engineer. If the aggregate is dry, water shall be applied to thoroughly and uniformly moisten the aggregate before application.

5. Rolling:

- a. (1) The Contractor shall perform all rolling with self-propelled, multiple-wheel, pneumatic-tired rollers. A minimum of three rollers will be required. The first two, drive side-by-side rolling the outer edges. The third roller then follows closely behind, rolling the center of the lane. The roller speed shall be no more than 5 mph (8 km/hr), so the chips are aggregate is correctly embedded into the binder.
 - (2) Rolling operations shall be arranged to ensure uniform rolling of all portions of the area to which Chip Seal materials have been applied.
 - (3) Rolling operations shall provide uniform embedment of the aggregate.
 - (4) Immediately after the Chip Seal materials have been distributed and before traffic is allowed upon the surface, the rolling shall begin.
 - (5) Rolling shall be completed during daylight hours and under favorable weather and temperature conditions during the day on which the Chip Seal materials are applied.
- b. (1) The entire area shall be rolled within 15 minutes after the cover material is applied and an additional 4 full rolling coverage's shall be made within 1 hour after the cover material is applied.

- (2) As soon as the emulsified asphalt has set and no further aggregate can be embedded, but by the day following the application of the Chip Seal materials, all loose aggregate shall be gently swept from the roadway surface by the Contractor. Care shall be taken to avoid dislodging embedded aggregate.
- (3) Sweeping will be conducted between 8 a.m. and 7 p.m.

METHOD OF MEASUREMENT

- 1. The emulsified asphalt is measured in gallons. Refinery certified volume shall be used as a basis of measurement of the emulsified asphalt if the entire shipment is used.
- 2. a. Aggregate for Chip Seal will be measured by the cubic yard at the point of delivery. The Contractor is required to strike off the materials to uniform height for volume determination.
 - b. The Contractor may request early sampling and testing at the point of delivery, in which case the aggregate shall be stored in lot size stockpiles.
 - c. The basic sampling frequency shall be 2 random samples for each "Lot" of 400 cubic yards.

BASIS OF PAYMENT

Pay Item
 Chip Seal Emulsified Asphalt
 Chip Seal Aggregate
 Pay Unit
 Gallon (Gal.)
 Cubic Yard (CY)

- 2. Aggregate not meeting the gradation requirements will not be accepted and paid for.
- 3. Emulsified asphalt which is determined to be out of the specified property limits shall have its payment adjusted by pay factors in accordance with current Nebraska Department of Roads specifications for asphalt materials for Chip Seal.
- 4. All test strips are subsidiary to the Chip Seal pay items.
- 5. Payment is full compensation for all work prescribed in this specification.

SECTION 202 - TRAFFIC CONTROL

202-01 Quantities

- 1. Traffic Control Quantities are based on the following.
 - a. Section 1
 - (1) Duration: Two Days
 - (2) 4th Street and Sky Park Road closed to through traffic
 - (3) Flagging performed to allow access to businesses and residents
 - (4) Eastbound and westbound traffic maintained at 7th Street by flagging
 - b. Section 2
 - (1) Duration: Two Days

- (2) First Work Phase chip seal placed through intersection of Airport Road while southbound US-281 and northbound Broadwell traffic detoured, and westbound and eastbound Airport Road traffic maintained by flagging (one day)
- (3) Second Work Phase chip seal placed from south end of section to intersection of Airport Road while Broadwell Avenue closed (one day)
- (4) Flagging to maintain access to Eagle Scout Park.

202.02 Temporary Sign Day

This work consists of furnishing, installing at locations as directed, operating, maintaining, and when signs are not required, removing temporary signs. General requirements shall be as specified in the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.01; Paragraphs 2 and 5.

Material shall be in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.02; Paragraph 1.b.

Temporary Signs shall be installed and maintained in accordance with the Manual on Uniform Traffic Control Devices and with Grand Island City Code Section 32-31. Prior to placement of any temporary signs, the Contractor shall acquire approval from the Engineer for each situation.

"Temporary Sign Day" is the pay item for temporary signs and "Temporary Sign Day" shall be paid by the each.

202.03 Type II and Type III Barricades This work consists of furnishing, installing at locations as directed, operating, maintaining, and removing Type II and Type III Barricades. Barricades shall meet the requirements prescribed in the current *Manual on Uniform Traffic Control Devices*.

Type II and Type III Barricades shall be provided, installed, maintained and removed in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.03; Paragraph 2., with the Manual on Uniform Traffic Control Devices and with Grand Island City Code Section 32-31. Prior to placement of any Barricades, the Contractor shall acquire approval from the Engineer for each situation.

Type II and Type III Barricades shall be measured for payment by the number of calendar days each is in place as per these specifications.

"Barricade, Type II" and "Barricade, Type III" are the pay items for temporary barricades. "Barricade, Type II" and "Barricade, Type III" shall be paid by the Barricade-Day (BDay).

202.04 Flagging "Flagging" shall be in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.03; Paragraphs 3.a.(1) and 3.b. The method of measurement and basis of payment for "Flagging" shall be in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.04; Paragraph 3.

202.05 Temporary Raised Pavement Markers This work consists of providing and placing Chip Seal Markers at locations as directed, protecting during placement of chip seal materials, and removing clear protective covers to expose reflective sheeting when the work is completed. Chip Seal Markers shall be placed as per the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.03; Paragraph 6.d.

Chip Seal Markers will only be required to delineate broken line.

Chip Seal Markers shall be on the Nebraska Department of Roads Approved Products List. "Temporary Raised Pavement Marker (Yellow)" shall have reflective sheeting on both sides of the marker.

"Temporary Raised Pavement Marker (White)" and "Temporary Raised Pavement Marker (Yellow)" are the pay items for Chip Seal Markers and shall be paid by the each.

202.06 Flashing Arrow Panel "Flashing Arrow Panel" shall be in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.03; Paragraph 10. The method of measurement and basis of payment for "Flashing Arrow Panel" shall be in accordance with the 2007 Edition of the Nebraska Department of Roads Standard Specifications for Highway Construction, Section 422.04; Paragraph 10.

