

Working Together for a Better Tomorrow, Today.

UTILITIES DEPARTMENT – PLATTE GENERATING STATION CITY OF GRAND ISLAND, NEBRASKA

CHIMNEY REPAIRS

ADDENDUM # 2 TO BID DOCUMENTS

ISSUE DATE: February 13, 2013

INSTRUCTIONS: Please sign below to acknowledge receipt of this Addendum to Bid Documents and return. If you prefer, confirmation of receipt of Addendum via email is acceptable.

Karen Nagel FAX (308) 385-5353
Utility Department, PGS Phone: (308) 385-5496
City of Grand Island knagel@giud.com
P.O. Box 1968
Grand Island, NE 68802-1968

ADDENDUM: Specification 107-13, Detailed Specification, Page 11 of 30 (Changes in red)

Exterior (second paragraph)

Saf-T-climb- Replace the top 50 feet of the exterior ladder safety system slide rail. The top 20' feet shall be 316L Stainless Steel and the bottom 30' shall be galvanized steel.

Air Space

As a separate attachment to the proposal, provide a firm, optional bid to add one safety gate at each of the three internal ladder platforms at elevations 170', 286' and 402'. The new gates shall comply with all OSHA requirements. The Owner will determine whether or not to add this Optional scope to the base scope at time of Award.

Interior Liner

High Pressure Water Wash the entire interior lining to remove all ash buildup to allow for a Class II inspection. The City will be responsible for wastewater removal from the base. The Owner currently plans to use a vacuum truck for removal and disposal of the waste water on site, anticipating that the Contractor will use a high pressure, low volume water wash. Final disposal plans will be determined prior to the outage based on information required from the Contractor after receipt of the proposals.

ACKNOWLEDGMENT OF RECEIPT OF ADDENDUM:			
Received by	Please Print	Signature	
Company		Date	

Please acknowledge this Addendum #2 on your BID DATA FORM and CHECKLIST.