

GRAND ISLAND LIBRARY STORMWATER GARDEN – ADDENDUM 1

ADDENDUM Number: 1

Subject: Modification to Contract Documents

Date: 18 March 2014

Project : Grand Island Library Stormwater Garden

Consultant: Dropseed Studio, the design branch of Kinghorn Gardens

Please review and incorporate the following revisions to the Contract Documents.

Item	Description
1.	<p>Sheet L200, Detail 2: Allowable substitution for perforated HDPE pipe with aggregate and fabric surround shall be NDS EASY FLOW integral underdrain product (pre-fabricated perforated pipe, Styrofoam ‘peanuts’ and fabric wrap). Size – 4” perforated pipe and 10” diameter assembly. All connections to tees or adjoining pipe sections shall be fully sealed with professional grade black underdrain piping tape. Substitution is at contractor’s option.</p>
2	<p>Sheet L200, Detail 3: Pretreatment basin fabrication. At contractor’s option, allowable substitutions for pretreatment basin shall include:</p> <ol style="list-style-type: none">1. Custom bent 3/16” stainless steel to form 24"x36" basin with 4" flanges bent at face of poured concrete curb wall to anchor via (3) 3/8" x 4" concrete lags each flange.2. Custom formed modular unit block four-sided surround. Modular block to be 4" or 6" ‘home improvement center’ garden wall block with finished surface all sides (i.e. simulated wall stone). Adhere each block unit in place with appropriate retaining wall adhesive (PL-Series). Stack such that 90 degree corners properly tie two faces together. <p>Both alternatives shall provide overflow along garden side of basin and dry set stone at bottom as per original detail.</p>

3	<p>Sheet L100, Flag Note 12 and L200, Detail 5: As clarification, recycled concrete is not required to be smooth saw cut all sides. Irregular sizes according to removals is allowed with pieces being predominantly rectilinear. Pieces with triangular forms shall be discarded or further broken to form appropriate general shape. Size of pieces shall be a minimum of 2' and maximum of 3' in any direction.</p>
4	<p>Bid Alternate 2: Add to the contract documents the following Bid Alternate 2: Contractor shall include in their bid as an alternate price the relocation of 80 linear feet of existing irrigation main line and adjustment of up to 8 irrigation heads.</p>
5	<p>Project Completion Date: The contractor shall complete the project by July 15, 2014.</p>

Issued By: Thomas Bentley, PLA. Dropseed Studio, the design branch of Kinghorn Gardens